

MRH **RUNNING** ##### **EXTRA** Apprentice with savvy modelers



Full
May
MRH
inside!



ALSO in this month's edition:

- Modeling stone structures
- A Brit models 19th Century Georgia
- Unconventional benchwork methods
- Safer airbrush cleaning solvents
- ... and much more inside!

WIDE EDITION
Hard-coded facing pages PDF

[INDEX](#)

[TABLE OF CONTENTS](#)

Hard-coded wide PDF version of Running Extra

The facing pages in this PDF have been merged into a single wide page, making them landscape.

Windows - Mac - Linux: Use the keyboard arrow keys to change pages
Tablet or phone: Swipe from the page edge to change pages

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

TABLE OF CONTENTS | RUNNING EXTRA

May 2021




RATE THIS ISSUE

Rate Running Extra issue ...

**RUNNING
EXTRA**

Publisher's Welcome: Pre-wired LED sources ...

JOE FUGATE



Limited Modeler: Modeling 19th Century railroading

JIM SIX



Unconventional benchwork methods that work

MARTY MCGUIRK



No more ugly track cleaning cars

MIKE MCGINLEY



A Brit models 1860s Georgia railroading

ERIC GATES



Scratchbuilding stone structures

JAMES EAGER



Ah-Hah Moment: Safer airbrush cleaning solvents

JOE FUGATE

TABLE OF CONTENTS | MRH

May 2021



Publisher's Musings: Modeling highway markings ...

JOE FUGATE




MRH Website this month: getting a new layout space, ...

Compiled by JOE FUGATE



What's Neat: Creating a loading zone, ...

KEN PATTERSON



Wiring a double crossover

G.T. GALYON



Easy to build town and city structures

V. S. ROSEMAN



Building a small N scale layout, part 2

DAVE KILBORN



Model Railroader's new 10-Year Archive: 2010-2019

JEFF PALMER



Savvy Modeler online: Easy speed matching

Compiled by the MRH STAFF



May 2021 news and events

RICHARD BALE and JEFF SHULTZ



[SUBSCRIBE](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

PUBLISHER'S WELCOME

introduction



MRH Running Extra | May 2021

JOE FUGATE SHOWS WHERE TO GET PRE-WIRED LEDS ONLINE FOR A GREAT PRICE ...



RATE THIS ARTICLE

ONE OF THE MOST WELCOME TECHNOLOGICAL ADVANCEMENTS OF THIS CENTURY has been the introduction of LEDs of every color in the rainbow, including a choice of various colors of white LED. These LEDs, when not overpowered, have an expected operating life of at least 40 years. No more changing out grain-of-wheat incandescent bulbs every 6 months!


On top of that, the availability of extremely tiny surface-mount LEDs [1] means we can now easily put scale-sized lighting in our locomotives and on our structure exteriors quite easily.

The one caveat, though, has been the frustration of trying to solder wires to one of these tiny LEDs! Well, the frustration is over!

It's now possible to purchase pre-wired SM LEDs for very affordable prices [2]. Avoiding the solder frustration makes these pre-wired LEDs a bargain. You can get them in the various sizes: 0402, 0603, 0805, and 1206 – and in any number of colors: cool white, warm white, red, green, yellow, blue, orange, pink, and UV.

More traditional larger LEDs can also be had, pre-wired *with* resistors [3]. These diffused-case LEDs provide a more uniform lighting and work great for many modeling applications including signals.

Speaking of signals, if you're looking for bi-color LEDs such as for search-



1. Surface mount LEDs can be extremely tiny, such as this 0402 LED that's only 0.04" x 0.02".


PUBLISHER'S WELCOME | 2



2. Soldering wires to tiny surface-mount LEDs can be a real pain. You can get pre-wired SM LEDs for as little as 49 cents each, and save yourself *a lot* of soldering frustration.



3. You can get more traditional LEDs in various colors with diffused cases and pre-wired with resistors for as low as 9 cents each.



4. If you're looking for bi-color LEDs such as for searchlight signals, you can find those with resistors included for as low as 7 cents each.

light signals, you can find those in the diffused case with resistors included, which is ideal for modeling use. Check out the shopping links for some great deals on pre-wired LEDs. ☑

To get a shopping list for this article, visit the MRH website at this link: mrhmag.com/magazine/running-extra/2021-05/publishers-welcome#shopping



SUBSCRIBE

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

THE LIMITED MODELER

column

Images are from the author's collection, except as noted.

MRH Running Extra | May 2021



JIM SIX EXPLORES MODELING OPPORTUNITIES IN 19TH CENTURY RAILROADING ...



1. This image is cropped from a very old photo of a crew standing in front of their New York Central American Standard 4-4-0 #422. Starting at the left is the engine fireman, the engineer, Conductor, and two brakemen. These were simple times, before electricity had expanded beyond a few big cities, before any world wars. No computers, cell phones, or radios, and it was long before anyone had conceived of the diesel-electric locomotive.



DOING MORE WITH LESS

THE LIMITED MODELER | 2

THIS MONTH IN THE “LIMITED MODELER,” we will take a plunge back in time to the late 19th century for a cursory look at what was there that is reasonable to model. Most modelers think that there is not much available to work with, but you have several different locomotives and a good amount of rolling stock available.

During the spring and summer of 1958, my brother and I built our first “real” HO layout. It was a pre-1900 setting. We had two locomotives – a Mantua 4-4-0 General and an Aristo-Craft straight-boiler 2-8-0 Consolidation. This was our first “permanent” layout, built on a 4 x 8 sheet of plywood that rested on a 40”-tall 4x8 cabinet Dad built.

This was the perfect setup for an 11-year-old and a 9-year-old to get started with model railroading. That was the one and only time we attempted to model such an early setting. We soon learned that diesel models cost a lot less than steam locomotives.

When we moved into our home 16 years ago, I was modeling 1980s Conrail. Since then, I have progressively shifted back in time to Penn Central, New York Central, World War II, and then into the 1920s. Today, I am looking at modeling the period from 1890 to 1910.

The more I learn, the farther back in time I go. Railroads were in their golden age of laying track and expanding. I like too many things in too many periods to ever settle on a specific year, but I am no longer interested in modern railroading.

Modern times have come to symbolize the decline of classic railroading for me. Mergers have reduced the number of available railroads and there has been no major expansion for decades. Instead, railroads have been pulling up track in many places.

Things were different a hundred or more years ago and times were simpler, but oh so full of modeling possibilities. I wonder what crews did when they got home after a day of work on the railroad in days before electricity, radios, televisions, and



[SUBSCRIBE](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

THE LIMITED MODELER | 3

model trains. They probably went home for a bath, a good meal, and a night's rest, or perhaps they went to the local tavern for beers and socializing [2].

I wonder how they got to and from work. Did they bicycle, walk, ride horseback, or even hitch a horse to a wagon for their commute? Who took care of the horse while they were at work?

I can hear their wives "mumbling" about all of the soot from passing trains getting all over the fresh laundry hanging outside on the clothesline. My mom didn't have an electric clothes washer until I was two years old, and I was out of high school before she had a clothes dryer.

Railroads and railroading were a big part of life during the period from 1880 to 1920. Not only were they the only intercity travel of the era, but railroad depots were community gathering points [3].



2. I will wager that after they got home and had a meal, many headed over to the local tavern for drinks and social time. At the left, it looks like there may be a discussion going on about an article in the newspaper.

THE LIMITED MODELER | 4

The noise, smoke, and motion of passing trains drew people's attention, and many youngsters dreamed of growing up to be engineers [4]. I imagine their fantasies were much the same as those my brother and I had as we played on our layout.

My love of model railroading continues to this day, now with a rekindled interest in modeling earlier times. The major difference is that now I have a computer to research railroading of earlier times, which allows me to build a credible model railroad to represent the days when steam ruled the rails.



3. This gathering of folks is at the Macon Dublin and Savannah Railroad in Georgia. I have not a clue what the occasion was, but such gatherings for photography were common circa 1900. These folks even brought their dogs with them for the occasion. The train crew is hanging out the windows to be part of the photograph. Looks like there are even a couple of locals in the background. I see a locomotive in the background at the far left.



I have often heard and read that modeling times before the Great Depression is difficult and that modeling 1900 or earlier is next to impossible. People say that there are not enough locomotives, freight cars, or cabooses available to represent such early times well.

Modeling back to the Civil War is doable, and it is a particularly attractive option if you have limited space. Trains in the post-Civil War were shorter and ran much slower. In part, this is because the locomotives were less powerful and could haul only a few cars. Railroad cars – both freight and passenger – tended to be shorter.

Short trains with few cars required relatively short passing sidings. This produces some real advantages to modeling trains from this era, rather than modern times. You need less equipment and operating space.

Many model railroaders choose N scale because of space limitations. I suggest that modeling the late 1800s or early 1900s won't take much more space than modeling modern times in N scale. Circa 1900, a train of 20 cars was long. Branch line trains were shorter, often only four or five cars



4. Photo circa 1905. This New York Central Lines passenger train is headed by an I-class American Standard 4-4-0. This is the same class as the famous 999. This three-car train was typical of the time away from the mainline. This is the kind of passenger train I want to model.

long. Locomotives were much smaller in 1900 than today, and each train had only one.

As to the argument that there are not enough locomotives available, before about 1900, there were only a few locomotive types. The locomotives of one railroad looked pretty much like those of most other railroads.

Athearn, Bachmann, Mantua/Tyco and other model manufacturers have produced – and continue to produce – steam locomotives that you can easily detail and paint to match most railroads of the era. This makes modeling these early times simple when it comes to locomotives.

Consider a couple of photos of the Grand Rapids & Indiana Railroad taken at Petoskey, Michigan, just south of Mackinaw City. The GR&I line incorporated on January 18, 1854, and by 1900 it ran excursion trains carrying 2,000 passengers north to Petoskey on a daily basis, with over 13 million passengers carried by 1913. The Pennsylvania Railroad bought the GR&I in 1918.

Petoskey was a major destination for the railroad, and its depot featured two through tracks, and three terminal sidings. Switching crews were ready to pull the cars off terminating trains. In my mind, I can see an operation where they would clean the cars and ready them for the return trip south [5, 6].

The locomotive heading the three-car train stopping at Petoskey in [5], looks to me like a 4-6-0 ten-wheeler. The Tyco 4-6-0 I am working on looks like a very much a match. In fact, this Tyco model could stand-in for several other locos in the photos included in this column.

While the 4-4-0 American Standard was the most common locomotive of the 19th Century, the 4-6-0 was the second most common type. The 4-4-0 was generally a faster and simpler locomotive than the 4-6-0 ten-wheeler, but the 4-6-0 was more powerful and could pull heavier trains.






the GR&I's excursion trains.

5. In this 1890s view of the GR&I at Petoskey, Michigan, we see three locomotives. One leads a through train southbound. To the left, we see a locomotive and its newly arrived train in the distance, while a switcher crew hitches on to pull away cars. Petoskey was a key destination city for



6. In this colorized postcard photo, we see another scene of a train that has just arrived in Petoskey. Debarking passengers crowd the platform as a switching crew couples to the coaches to prepare them for the return south.



7. This photo is the oldest in my collection. The locomotive is the S. F. Phelps #31 built in 1866. The photo was probably taken shortly after the locomotive was placed in service. The railroad was the Rome Watertown & Ogdensburg RR, part of the New York Central. The fuel load in the tender appears to be wood. Look how the train crew is dressed – suits and ties! Look at the “rack” that supports the huge headlight.



8. RW&O #40 and crew pose for this circa 1870s photo. Note the wood pilot beam and full-width footboard. This loco is probably used as a switcher.







9. Here is a photo of the C&NW circa 1880, maybe a little later. Note that the locomotive looks just like anyone else's 4-4-0 American Standard locomotive. Five of the six crewmen visible are wearing a white shirt and vest. Notice how closely the locomotive compares to the NYC locomotive in photo [7]. It also looks like the Mantua/Tyco "General" HO scale locomotive. I can see myself operating the layout with a few of the Tyco 4-4-0 locomotives.



10. This is the photo from which [1] was cropped. I wouldn't be surprised if it was taken 150 years ago. The locomotive appears to be 1860s or 1870s vintage – possibly later. Note the old-style domes. What is that sign with the large "X" on it? While I like this locomotive, this is too far back in time for me. Balloon smokestacks are a "flag" for me to stop and back up.



11. B&A #311 was built by Schenectady in February 1896 and was typical of B&A and NYC&HR locomotives of the time. The #311 is a later-day 4-4-0 on the NYC Lines. It has a large boiler for an American Standard locomotives, and probably worked into the Great Depression before being sidelined. If you are modeling before the 1910s, it is hard to go wrong using 4-4-0 locomotives.




12. This is a later-day 4-4-0 American Standard locomotive. Other than some pin striping, there is nothing fancy about # 1148. This is a NYC&HR locomotive. I wish that I could read the sign on the head-end car. I would guess this photo to be circa 1905.





13. Who says 19th century trains were all short? This Eastern Railroad train of boxcars is quite long, and more cars are out of sight to the left of this old photo. I love it how train crews would climb all over the train to pose for photography. The locomotive, ERR #96, is an early 2-6-0 Mogul. *Shorpy photos, Jim Six collection*



14. Ohio Northern was a part of the New York Central Lines. ON #34 is a 2-6-0 Mogul, somewhat of a minority type locomotive on the NYC Lines. Should you want to model this locomotive, good luck. The only early Mogul available that I am aware of is the Athearn/Roundhouse "old time" straight-boiler Mogul. Coming up with the "wagon-top" boiler would be an obstacle.


Both were considered dual-service designs with the diameter of the driving wheels determining which service a locomotive would be assigned. Larger-diameter drivers for passenger service, small-diameter for freight, and intermediate-size drivers for dual-service.

This means that one could model in the late 19th Century with 4-4-0 and 4-6-0 locomotives. If modeling the 1890s you will probably want to add the 2-8-0 to the mix. Since I have all three types, I could easily model the late 1800s.


Bachmann, Athearn/Roundhouse, and Tyco/Mantua have all produced good models of the 4-4-0, 4-6-0, and 2-8-0 locomotives representing pre-1900 times. The Bachmann models are available with DCC and sound. I am not sure about the Athearn/Roundhouse models. The Tyco/Mantua models will need to have both DCC and sound installed, but then, those models are available at reasonably low prices.

**Did you know
there's an MRH/
RE index
available?**


CLICK TO FIND OUT MORE



15. Lake Shore & Michigan Southern #107 was built in 1896 by Schenectady. The 107 was a later design than the 5166 in photo [13]. The 4-6-0 type locomotive was widely accepted by the LS&MS. On the other hand, NYC&HR preferred 4-4-0 American Standard type locomotives and never really warmed up to the 4-6-0. Remember, the NYC&HR was the eastern component of the NYC Lines running from the east coast to Buffalo NY. The LS&MS was the western component running from Buffalo to Chicago.



16. One more Ten-Wheeler, Michigan Central #512. This is a “modern” 4-6-0 that was typical of MRCC locomotives. It is an 1898 product of Brooks. Note the single-phase air pump and the somewhat large drive wheels. Lines are clean and uncluttered. It was equally comfortable at the head of a passenger train or a freight. Note the slightly more-modern look when compared to the 107 in photo [15]. The cab roof is a bit more rounded above the side windows, and the headlight is much smaller than the huge light on the 107.




17. I included this photo to make a point. One has to look closely at the lettering on the tender side to know that this is a New York Central Lines locomotive. Without this lettering one could take this to be a ten-wheeler of the ACL, B&O, PRR, SOU, or that of any of a number of railroads. I wonder where the engine crew is. The locomotive is putting out a lot of smoke to be unattended.



18. NYC sibling Ogdensburg & Lake Champlain #340 looks good in this pose. Schenectady built the 340 in 1897. This could be a

builder's photo but I'm not so sure looking at the cab roof. Still, the locomotive is clean and appears in good condition. Consolidations rode relatively low with their small driving wheels and were not very fast, probably good for 35 mph, maybe more on a good day. I don't see any class lights front or back on this locomotive.





19. CCC&StL #728, built in the 1890s, was a brute of a locomotive for the time. That's a rather large boiler for the 1890s. Compare with the boiler of #340 [17]. The 728 was powerful and capable of pulling heavy trains at slow speeds. I have to believe that the flair at the top of the smokestack was ornamental. ☑

★★★★★
RATE THIS ARTICLE

**Did you know
there's an
MRH/RE index
available?**

CLICK TO FIND OUT MORE



SUBSCRIBE

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

GETTING REAL



column

MRH Running Extra | May 2021

All photos by the author unless noted

MARTY MCGUIRK SHOWS US A FEW UNCONVENTIONAL METHODS THAT WORKED WELL FOR HIM...



IT'S BEEN ABOUT 30 MONTHS SINCE I STARTED

CONSTRUCTION ON my HO scale Central Vermont Richford Branch layout. My goal was to have the layout mechanically complete (benchwork, track, and wiring) by the three-year mark. I'm happy to report I've met that goal.

I've accomplished this by staying fairly faithful to the original layout design – the prime directive – and to my mantra of keeping the overall goal in mind and callously ignoring any “best practices” or group-think that’s contrary to my goals.

For example, I don't have a staging yard. On my last layout, staging always seemed like a colossal waste of space, so on this layout, I questioned if I even needed any staging at all. I have what could be characterized as a couple of staging tracks – but that's simply so I can display some extra cars on the railroad.

So three years into this project I'd thought I'd share a few things that I think have gone remarkably well.

WORKING WITH A LAYOUT DESIGNER

I'd like to think that I'm good at some things in model railroading – but layout design isn't one of them. Hence my

GETTING REAL | 2



1. This overall view of the layout shows the topics discussed in this month's Getting Real. The swing gate is visible to the left of the support pillar. This shot also shows the way everything below the ground level is painted, and the open look of the room, unencumbered by backdrops and infrastructure.

early decision to work with a professional layout designer, which in my case was Lance Mindheim, proved invaluable. Although Lance is a good friend, I actually contracted with him to design my layout!

I found Lance's thought-provoking questions throughout the design process helped me narrow-in on what I wanted, and didn't want, from this layout. We went through two or three iterations to get to the final benchwork footprint, but the resulting plan allows for interesting, if not “intense” operations.

For the most part, I have stuck pretty close to Lance's design. Of course there was one spot where I outsmarted myself and thought that adding tracks to the planned staging area would



SUBSCRIBE

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

improve the layout, but I quickly realized the error of my ways, and removed the staging yard and replaced it with a small town scene.

I was thrilled when Lance stopped by to visit in person and pronounced the result a much better use of the space than the staging originally planned for the spot!

BACKDROPS – ARE THEY REALLY NECESSARY EVERYWHERE?

I received an email the other day from one of the viewers of my CVSNE YouTube channel asking me why I didn't include



2. One of my goals is to capture the wide-open look of the countryside wherever possible. This photo (the scenery is still not complete) shows a view looking across two sections of the layout with a wide (four-foot-plus) aisle in the middle. You can just barely make out the top edge of the fascia on the distant layout section in this view, which will be virtually invisible from this angle when the final scenic texture is added.

backdrops behind either peninsula or the “front” section of the layout. In fact, the only backdrops on the layout are the walls of the room. I didn't construct any new backdrops, nor do I intend to.

There are a few reasons for this. In no particular order they are:

- One of the toughest things to deal with in model photography and videography are shadows reflected from the 3D world onto the 2D wall, which is supposed to represent sky. The sky outside my window doesn't reflect the shadow of my neighbor's house, the trees, or anything else.
- Somewhat related to the above are the lighting issues that additional backdrops introduce. If there's one area where we model railroaders really need to focus, it's thinking through and improving layout room lighting. I really failed in this area on my previous layouts, and although I feel the current layout room lighting is better, it's far short of ideal.

Adding more backdrops is simply adding more walls. It creates distracting shadows that need to be addressed. Backdrops block light from reaching the layout, and they often reflect conflicting shadows.

It becomes a sort of self-perpetuating problem after a while. Adding more backdrops decreases the level of light on the layout, which requires adding more light fixtures, which leads to more and weirder shadows, et cetera.

- I've been told that breaking up the room with backdrops creates a sense of isolation and distance, but I am self-aware enough to know I'm in a basement looking at a model railroad. I don't really buy that argument.

On a large, multi-crew layout, it's said the “serpentine layout footprint” – of which backdrops are an integral part – prevents “sneaker orders.” Basically, you don't move your train based on whether or not you can see an opposing train



crew's feet (ie., "sneakers") instead of relying on the timetable and train orders. By that logic, you need to screen the underside of the layout from opposite aisles or train your operators to move like ninjas!

In all seriousness, if I had a large, multi-operator layout, such a consideration may be important. But I model a secondary mainline (at best), so building extra infrastructure would lead to resources being devoted to a non-problem – a clear violation of the prime directive – and given the number of issues I've listed already, it just did not seem worth it.

- Although some promote building their layouts on narrow shelves with a few inches on either side of the track as a method to lengthen the mainline, it almost always comes at the expense of visual impact. The only photo angle available is the "extreme 3/4 wedge shot."

Worse than that, when viewing the layout in person, you fail to achieve the sense of a train in the environment. It very often looks like exactly what it is: a model train running along a narrow shelf with a modicum of scenery on each side.

- The last, and perhaps most important reason I decided not to add backdrops to the layout is simply the fact that I enjoy stepping back and surveying the landscape [2]. It's pleasant to look at the layout in person, and it improves with the completion of more scenery! And, if you drop the camera down to eye level, you can achieve some truly deep, realistic vistas.

CROSSING THE GAP

A significant design "given" was some form of continuous-running capability. To achieve this, the mainline runs around the perimeter of the layout area. Since another given was unimpeded access to the center of the layout area, the only



3. The underside of the gate itself shows the 3/4" birch plywood brace and 1x2 strips designed to keep the gate from sagging and hogging. I sealed everything with acrylic varnish prior to painting it the fascia color.

practical way to enter the space would be some form of lift-out or swing gate.

I've never built such a thing before, but Lance assured me that it wouldn't be difficult to get a reliable lift-out. In fact, I spent far more time fretting about it than it took to build it. The trick is to keep it simple.

I didn't want to use a lift-out. The problem with a lift-out is that I'd have to actually lift it out, allow any visitors into the interior of the layout, and then somehow replace it without leaving a track misaligned or a wire disconnected.

I decided some sort of pivoting or movable section would be a better approach. Although the movable layout section may be a




little trickier to engineer than a simple lift-out, I figured the risk was worth it. I really have to thank my friend Stic Harris for all his assistance engineering and installing this thing.

In essence, it's bone-headed simple – ideal for someone like me! The gate is a piece of birch plywood attached to the corner post of an IKEA Ivar large storage cabinet [1]. I ballasted the cabinet with my collection of railroad magazine back issues to make sure the hinged end doesn't shift. It's not going anywhere!

I braced the gate itself with $\frac{3}{4}$ " birch plywood [3] and placed it on its side to reduce any risk of hogging or sagging. I sealed all these wood components with clear varnish to minimize warping and expansion and contraction.

Keeping Lance's well advised "keep it simple" mantra in mind, we considered, and quickly rejected, all sorts of latches, pins, and locks to secure the non-hinged end of the gate. Instead of a latch, the gate surface slides beneath a piece of MDF that's secured to the plywood sub-roadbed, leaving a gap [4] between the underside of the MDF and the layout frame. Simple friction [5] holds the gate in place.



4. The end of the gate (left) slides into the slot, and friction holds it in place.



5. The gate in action! The end of the swing gate slides into the notch visible in photo 4. Note the paint scrapes indicating the friction lock. At some point we'll likely add an electrical interlock to kill power when the bridge is open.

I laid the track across the span with the gate in place, replacing about a half-dozen plastic flextrack ties with PCB ties in the process. The PCB ties will prevent the rail from coming loose at the end of the gate [6].

I glued the rest of the flextrack in place with adhesive caulk. Once the track dried, and the rails were soldered to the pcb ties, I used a cutoff wheel to slice through the rails.

The photos show how this was engineered and how it works. I haven't decided if I'm going to scenic the swing gate, but if I do, I'll be sure to use only lightweight materials.

Does it work?

Back before COVID, we hosted our annual Christmas open house for friends and neighbors. The trains ran just fine over this swing gate, virtually unsupervised, for more than




four hours straight – so I consider the swing gate a complete success.

FASCIA COLOR AND FINISHING

One thing that I think has worked remarkably well is the way everything below “ground level” on the layout is painted the same color [1].

Straight fascia is made from 3/16” MDF. The curved sections of fascia are cut from “Bendy Board,” essentially pre-kerfed MDF I purchased from Rockler (www.rockler.com/1-4-neatform-bendy-MDF). The bendy board is a bit pricey – which is why I used it only in sections where I needed the fascia to curve smoothly.

I secured the fascia with round-head screws – I opted not to countersink the screws to facilitate removing the fascia to make it easier to access the underside of the layout. This has already proven its worth when it came time to add switch motors.



6. Closed position. Using PCB ties on both the gate and the layout to help keep the rails aligned at the gate.



7. After catching my elbow on the sharp (ouch!) 90-degree fascia corners I opted to round the corners.

Since the layout features fall scenery, I seriously contemplated some sort of rust/tan/brownish color for the fascia. I also briefly considered black. But the thought of painting the walls under the layout, the cabinets, and the legs black seemed like it would be just a little too stark and jarring.

Since we have cool gray carpeting and walls in the rest in the basement, a cool color matched better than a warm tone. My wife Christine chose the color on something called a color wheel to contrast with the rust/red undertones of the autumn scenery. I had no idea what she meant by all this, but she’s the artist, so I went with her choice!

She chose a dark bluish green, called “Riverway” from Sherwin Williams, which you can see in the overall photo of the layout above. It looks a little bluer in photographs than in person. It



contrasts just enough to frame the bottom edge of the scenery, yet is dark enough to make the underside of the layout “disappear” without being so dark that it looks like a black hole.

Using the Ivar shelving system for my benchwork has the advantage that I can include lots of storage shelves under the layout. My original intention was to use the open shelves in the front of the layout to display dioramas, railroad artifacts, and the like. Unfortunately these have instead become a repository for “stuff” ranging from stacks of research material to scenery supplies to rolling stock boxes.

I’m going to continue to tolerate this while the basic layout construction progresses. At some point, I’ll either need to get serious about making these real display areas or put some form of beadboard paneling to screen all that detritus from view!

Although obviously not related to the fascia color, I’ve rounded the corners [7-9] on the fascia wherever someone may



8. The first step is to fill any gaps with Minwax Wood Filler. Once it dried, I used an orbital sander to round the corners and smooth the surface. It’s hardly finish carpentry, but it was easy, quick, and effective.



9. I gave the fascia two coats of the Sherwin Williams Riverway paint. In fact, everything from the “ground level” down is painted the same color – the fascia, layout legs, walls etc....

accidentally catch themselves on a sharp corner. The photos show how this was done.

So there you have it, just short of three years into this layout project, complete with all of life’s distractions and delays, the basic layout is fundamentally complete, functions well, and has resulted in a layout design that meets my prime consideration – making me happy. I’m looking forward to disposing of all the scraps of wood, leftover track bits, and spools of wire and focusing on modeling projects. ☑



VARIATIONS ON A THEME

By Mike Dodd

Marty and I have followed similar paths in building our layouts, and we seem to have reached similar conclusions, with minor variations. Marty and Lance both operated on my former HO scale Virginian Railway around 2005. Photo [10] was snapped during an op session, and shows the features mentioned below.

- **Fascia color.** I agree with Marty's choice of dark bluish-green for the fascia color [10]. It is more muted than a straight green or brown, and doesn't draw the eye away from the scenery. I looked at color cards in Lowe's paint department, then had them custom-mix a color between two of the stock colors.



10. An op-session photo showing the bluish-green fascia, navy-blue drapes hiding under-layout storage, flat-head screws in cup washers (foreground), and miniature toggle switches installed on the 1/8"-thick fascia (background).

- **Fascia material.** I used 1/8"-thick hardboard (Masonite) instead of MDF for fascia panels. This bends easily around a medium-radius curve; for sharper angles, I butted two pieces together ([10], left and center). Hardboard edges are not as hard and sharp as MDF, so I didn't round the joints as Marty did. The 1/8" material is thin enough to mount miniature toggle switches to control turnouts ([10]).
- **Fascia mounting.** I favor flat-head screws over round-head screws to secure fascia panels. I didn't want to drill countersunk holes in the thin hardboard, so I used cup washers with 3/4" #6 flat-head screws, [11] and [10]. I bought my screws and cup washers from McFeely's www.mcfeelys.com and still have plenty left for the next layout. I used square-drive screws for reasons not remembered; regular flat-head Phillips screws work just as well in the cup washers.
- **Under-layout storage.** The bottom of my benchwork was 54" above the floor, leaving plenty of height for homemade and commercial shelving units to hold books and unbuilt models, but not items for display. My goal was to have storage that was not visible to operating crews.



11. Flat-head screws and cup washers. No special reason for the square-drive screws – Phillips heads work as well.



VARIATIONS ON A THEME *CONTINUED...*

- Shelf feet. Another goal was for the shelves to be easily movable. I wanted to be able to slide a loaded shelf on the carpeted floor, so I made special feet [12]. 2x4 lumber is 3-1/2" wide, so I cut 3-1/2" squares from premium-grade 2x4s, then used a router to round-over all four edges on one face to 1/2" radius. On the opposite face I drilled a 1/2"-deep hole large enough to accept a shelving unit's leg. I put a blob of construction adhesive in the hole, and set the shelving unit's leg into it (after removing the leg's plastic cap). For shelving without tubular legs, like homemade wood or commercial MDF units, I glued the feet to the underside of the bottom shelf.



12. A foot made from 2x4 lumber. Each foot is 3-1/2" square, and the four bottom edges are rounded-over to 1/2" radius for easy sliding on carpet. The shelf leg fits into a hole drilled in the top.

- Hiding the under-layout shelves. Like Marty, I wanted to hide the shelves beneath the layout, but I chose navy-blue fabric drapes instead of rigid material. I bought two full bolts of the fabric, then cut lengths of it to span sections of the fascia. Then I broke out my sewing machine (yes, mine, not my wife's), and hemmed the raw edges. I removed the fascia panels, stapled the drapes to the benchwork, then replaced the fascia. You can see the drapes in [10]. ■

**Tell your friends about
Running Extra!**

**We depend on word-of-mouth to grow
... if you don't share us, we don't grow**



No more *ugly* track cleaner cars



MIKE MCGINLEY ASKS WHY PUT UP WITH CHUNKS OF BRASS,
OR TOY-LIKE TRACK CLEANING CARS FOR YOUR LAYOUT?

1. This is a Walther's Track Slider, just repainted, to suggest it is in maintenance-of-way service. There were very few prototype low-roof, plug-door, 40-foot boxcars with roller bearings, so this will have a hard time being an acceptable car to me.



[SUBSCRIBE](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)



MODEL RAILROADING IS A VISUAL ART, and I want to share some fun, easy ways to make track cleaning cars easier on the eyes. Here is what I have done on my HO scale layout; try these ideas for some easy fun.

First, some background. One common tactic to keep track clean is to wipe it with sliding blocks often enough to keep debris (household or shop dust, overspray, or drops of oil) off the rails and to break up corrosion that may start to form.

Most of the time a non-abrasive rubber or wood block does fine. Many modelers avoid blocks with abrasive grit, as they may leave scratch marks on the rail that can capture and hold contaminants.

Several manufacturers offer cars with spring-loaded or simple gravity-actuated sliding pads that you can run either as a part of a “track cleaning train” or mixed in with a regularly operated fleet of cars.



2. Lifting the shell off the Walther's car reveals a heavy metal floor.

You don't have to accept the paint schemes or even the body styles of the marketed track cleaning cars. This article is about making tolerable to handsome track cleaning cars.

The truth is that these are never going to be quite prototypical in appearance with a block under the car, so feel free to experiment with these cars. I have used old decal sets and old car bodies to experiment with weathering and finishing. I don't usually add fussy details like air hoses or uncoupling levers to most of them, but that's up to you.



3. The cleaning pad assembly screws to the car, and a spring suspension helps press the cleaning pad to the rails.



4. This is the same car painted mineral red. However, I gave up at this point. I simply could not envision an acceptable paint scheme for this car.



NO MORE UGLY TRACK CLEANER CARS | 5



5. I decided to replace the Walther's car body with one from an old Athearn blue-box kit. The body will drop right onto the Walther's track slider chassis. Note that not all bodies will fit all chassis; there are variations between

manufacturers' dimensions on floor opening and sill height.



6. This is that same car body on the Walther's chassis after a quick pass of "Rustall," weathering powders, and Tamiya Flat Clear rattle-can finish.

Tell your friends about Running Extra!

We depend on word-of-mouth to grow
... if you don't share us, we don't grow

NO MORE UGLY TRACK CLEANER CARS | 6



7. I decaled and weathered this Accurail car to suggest it was still in service in the 1980s, and fitted it with an A-Line 1003 track slider kit, which works by gravity. I added some weight for stability, and also to the slider itself to make it a little more aggressive.

A-Line advertising shows the kits installed under hopper cars too, but I think the sliding block is too visible there. One challenge with the A-Line installation is drilling holes for the vertical pins through the weights in most cars: they are usually steel. That's what drill presses were invented for.

**Did you know there's
an MRH/RE index
available?**

[CLICK TO FIND OUT MORE](#)



[SUBSCRIBE](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

NO MORE UGLY TRACK CLEANER CARS | 7

I have seen advertisements for Bachmann track slider cars, including 40-foot steam-era boxcars, refrigerator cars, and a tank car, but have not purchased one yet. Walthers and Bachmann are just a click away on the *MRH* sponsors page.

You may notice that all of these cars so far are 40', which might seem problematic for modeling 1980s and later, since larger-capacity cars had all but replaced 40' cars by then. However, 40' cars with sliders work much better on sharper curves. Larger cars look nice, but their center overhang tends to make them impractical [9, 10, 11].

★★★★★
RATE THIS ARTICLE



8. This is an Athearn “Baby Hy Cube” boxcar that might be found in the 1970s-1990s. I installed an aftermarket track slider (but I forget who made it). The low side sill on this car helps conceal the slider block. I always paint the sides of the block a very dark, warm gray to blend it into the scenery as much as possible.

NO MORE UGLY TRACK CLEANER CARS | 8



9. This is my favorite cleaning car, a Tangent ACF 70-ton welded 50' “fish belly” gondola to which I added an A-line slider block. The load of creosoted utility poles (it just as easily could have been a load of pipe or lumber) conceals the vertical pins on the sliding block, while the low fish-belly sides help hide the block itself. This is actually a good representation of SP G70-8 through -14 cars, many of which lasted into the 2000s with roller bearing trucks.



10. This is a vertical view of the 50' car on a 30"-radius curve. Note the overhang in the middle. The car makes a chord between truck centers, and this can prove too much to keep the cleaning pad on both rails.



SUBSCRIBE

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)



A-line slider installed under various length cars to determine what combination of radius and car length works best to keep the block on the rail.




11. Focusing on sliding block on this same 30" curve, we see it barely stays on the outside rail. Based on my experience with this car, I recommend using only 40' cars for radii up to 26-28". You may do an experiment for your situation; set up a section of flex track curved to your layout's tightest dimensions and test an

12. Here is my next project. I'll use the frame of this Athearn 50' boxcar under one of my Railbox cars to represent operations circa 1990-2010. The Railbox frame can mate up with this 1960s-era car for earlier operations. ☑

★★★★★
RATE THIS ARTICLE

HIDE THAT CHUNKY BRASS CAR



13, 14. The Centerline Products track cleaning car looks ugly [13] – it works quite well, but it's just an ugly chunk of brass. I set about making it a much better looking car.



SUBSCRIBE

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

HIDE THAT CHUNKY BRASS CAR CONTINUED ...

Centerline Products has made a very handy track cleaning car [13] that uses a solid brass roller wrapped in strips of shop towel fabric.

They made the car's frame solid brass with a hole to guide the roller. You moisten the roller with a cleaning fluid and when the car is in motion, it rolls and slips along the rails to clean them.

I liked the car technically, but not artistically.

I enhanced its looks by gluing side panels, end panels, and ladders to make a simple gondola. Then I painted it a Maintenance-of-Way gray and gave it MW reporting marks and a car number.

I disguised the roller with a hollow load of creosoted timbers [14, 15] and voila! No more chunky brass car. ■



15. Now you would never know this is the brass Centerline Products roller track cleaning car! It looks much better now rolling down the line cleaning the track.

MIKE McGINLEY



Mike has been a model railroader off and on since the 1950s. He is retired after working as a Civil Engineer and Maintenance of Way Manager for the Southern Pacific, Metrolink, and several consulting engineering firms. Since 1994 he has been building, moving, and modifying his Southwestern Pacific


Lines, a freelance western railroad upon which the SP and several other companies have operating rights. He enjoys building and photographing as much or more than operating. He and his wife live in southwest Washington, they have one son.

His modeling strategy is to operate and photograph a specific era and then to set the calendar back five years and sell off the newest rolling stock. So far his has completed 2006 and 2001, and is operating in 1996. "At the end of this scheme we'll arrive at the late steam era with black widow and Daylight diesels, but first I have to model the eras I worked through." Mike enjoys and learns from visits and operations on other layouts, and is active in the Columbia Gorge Model Railroad Club in Portland, OR.

Mike says his best times are when visitors come, especially children. He often hands the controller to anyone tall enough to see the trains, they have always been good engineers. In addition to making models could Mike have started a lady hog-head on a RR career? ■

★★★★★
RATE THIS ARTICLE

MAKE NON-ABRASIVE TRACK CLEANER CARS



By James Regier

I make non-abrasive cleaning cars using old Athearn boxcars, 1" roofing nails, and a Masonite wood slider.

Masonite makes a good, inexpensive material for track cleaning. It has a rough surface that works well for scrubbing dust and oxide off the rails, but being non-abrasive, you don't have to worry about the pitfalls of scratching up your railheads.

Simply cut a piece of Masonite down to size, about 1-1/4" wide by 2-1/2" long. You need it just wide enough to cover

both rails and provide a little bit of room for play on those tighter curves, but not wider than the car itself.

I found using an emery board to slightly chamfer the edges of the rough side of the Masonite helpful to prevent it from catching on any rough track work.

Remove the car body and drill two 3/16" holes, centered about 1" apart through the floor and steel weight of the boxcar. This will allow just enough space for the penny nails to ride up and down freely.

With the holes drilled, apply epoxy to the smooth surface of the Masonite. Place the heads of two nails into the epoxy and center the car chassis over the Masonite, with the nails pointing up through the floor. Set it aside for the epoxy to cure.

Before assembly, I added one ounce of weight to the smooth side of the Masonite to help it adhere to the rails, and half ounce of weight to each end of the car itself to stabilize it against any forces from the cleaning pad.

With that, you're ready to clean the rails. Simply hitch it to your train and pull away. As the masonite gets dirty, you can rub the residue off the Masonite with steel wool to clean it and then put it back on the track. ■



16. You can use Brillo Pads to periodically clean the residue buildup off the Masonite wood sliders.

The Roswell Mill



MRH Running Extra | May 2021

ERIC GATES A BRIT MODELING
1860s GEORGIA ...



THE ROSWELL MILL PROJECT started when two different trains of thought combined.

The first followed a series of visits to my daughter's home near Atlanta, after her husband took a job there in 2013. Our first grandchild arrived shortly afterwards and we visited regularly during the four years before they relocated elsewhere. We made frequent outings to towns along the route of the former Western and Atlantic Railroad, including Kennesaw, with the Southern Museum of Civil War and Locomotive History.

THE ROSWELL MILL | 2

Lead. The year is 1861 in Georgia. The loco, Roswell, of the Western and Atlantic Railroad, waits to depart from Roswell Mill for the return to Atlanta.

Kennesaw was once known as Big Shanty, or the starting point of the Great Locomotive Chase in the American Civil War. The museum features The General, one of the locomotives involved in the chase. The temptation to model a rather different prototype than my normal interest took root.

The second strand came from a book by Ian Rice, published in 2016 by Wild Swan, entitled *Creating Cameo Layouts*. This draws heavy influence from the relatively small size of houses in the UK (usually without basements), as well as a culture for building transportable layouts for train shows. Rice launched his book in parallel with a competition to build a layout within two years, that met his criteria.

Essentially, Rice's cameo layout proposal envisages a self-contained scene, like a stage set with wings on either side to limit the viewing angle, and an arch above the front to conceal built-in lighting. It would include a staging yard to assemble trains off-stage, integrated electronics, and a support system to bring the whole layout up to a comfortable viewing height. The whole thing would be small enough to transport in a compact car.

In my mind, these two ideas came together in a plan to build a model based on a US prototype using many of the same techniques that I use when I model UK prototypes. I envisioned a layout from around the time of the Great Locomotive Chase in the 1860s.

The result was Roswell Mill, a fictitious spur of the Western and Atlantic Railroad (W&A) in Georgia. Now in the suburbs of Atlanta, Roswell was an independent town in the 1860s with a mill that produced cotton fabric. The Roswell Mill became a strategic industry during the civil war.



[SUBSCRIBE](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

THE ROSWELL MILL | 3

The W&A line was several miles away and had no line to the mill, so I imagined a spur to support the mill and neighboring township for my layout. I set the layout in rural Georgia on the eve of the American Civil War, though I made no serious attempt to faithfully reflect the real Roswell Mill.

Track on the W&A was 5' gauge, so I wanted to capture that broad gauge in my modeling, with lightweight, unballasted rail and long ties [2]. Based on a scale of 3.5mm to the foot, I calculated my track gauge to be 17.5mm for what I call H0b5, as opposed to the standard 16.5 mm gauge for standard H0



1. The General, as preserved at Kennesaw, is not well-placed for photography. The locomotive has been much rebuilt since its original construction: it sports two domes rather than three, and it is now standard gauge instead of its original 5' gauge. Further additions include brakes, additional controls and cab indicators.

THE ROSWELL MILL | 4



2. Atlanta station approach showing the 5-foot gauge track. Note the two stub switches in the foreground, arranged toe to toe to create a double slip.

scale track. I had to make sure that all equipment was upgraded to P:87 standards to allow me to use code 40 rails, typically used in 2mm scale.

The finished layout is proof that modeling 5' gauge lines in HO scale is feasible, though I am not sure I would adopt this approach for a basement empire. My aim for this project was simply to be able to shuffle a loco and two freight cars around.

A Mantua General measures about 7" over the tender, and a civil-war-vintage freight car measures about 4". This made the target train length about 15", setting the minimum dimension for the staging yard and driving the length of the loop. A 15" turntable for a staging yard would allow the whole train to be rotated.



[SUBSCRIBE](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)


[TABLE OF CONTENTS](#)

BUILDING THE "ROSWELL"

I needed a locomotive for my layout, and I used the General for prototypical inspiration. Though the actual General is on display in Kennesaw, the locomotive now looks significantly different from its appearance in the Great Locomotive chase.


Shortly after the Great Locomotive Chase, Confederate forces deliberately wrecked the General in an effort to prevent Union forces getting their hands on Confederate supplies during General Sherman's march [3]. Since then, the locomotive has undergone at least three rebuilds.

John Ott has produced some lovely, well-researched drawings and models of early American locomotives and railroads. He has made them available on his website, www.ottgalleries.com, and a visit proved most useful. It's best to settle down with a



beer or a coffee before visiting his website; time can pass quickly [4].

3. A heavily damaged loco alleged to be The General, at Atlanta sometime after General Sherman's visit.



4. John Ott's meticulously researched image of The General at the time of the Great Locomotive Chase. Built by Rogers of Paterson, New Jersey in 1855, it would have been seven years old when the event took place. *Copyright John Ott*


Originally, I had planned to buy a cheap Mantua General on eBay and backdate it, but it quickly developed into a more complex project, especially since I wanted to adapt it to run on HO_{b5} rails. I also wanted to remove the motor from the tender and place it in the locomotive. On top of that, I wanted to detail, repaint, and weather it. I knew that with available parts, I could not quite recreate the General, so I decided to use the General as a basis for a plausible sister locomotive, which I called "Roswell [5]."

Since I had convinced myself to work to P:87 track standards and to HO_{b5} gauge, a new chassis for the General was a must.


It follows the profile of the original, but I made it of thin brass strip, which increased the available space between the sideframes – particularly with the extra millimeter with H0b5 gauge [6].



5. The Mantua General as it came in the box. It represents the General as it appears at Kennesaw, significantly different from its appearance at the time of the Great Locomotive Chase.



6. A comparison of the new loco frames on the left with the original ones on the right. Note one of the walking beams at left to support the drive axles. The thin brass frames left space for the motor to mount between the frames, instead of on top.



7. The new frame. Note the walking beams that will suspend the driver wheels. I have not cut the mounting rod to size in this photo.

The original model had a motor in the tender with a drive shaft to connect it to the gearbox in the loco body. With the available space between the sideframes, I could mount a small Mashima motor into the cab and connect it to the drivers via a RoadRunner Compact gearbox from High Level (www.highlevelkits.co.uk/product-page/copy-of-roadrunner-compact).

The demands of P:87 wheel and track standards meant that I needed to keep all four driving wheels on the rails at all times. I mounted the driver axle bearings to a pair of walking beams that pivot on a central rod, which mounts the walking beams to the locomotive frame. This compensation system gave each wheel some independent vertical movement to compensate for any unevenness in the track [7].

The leading truck forms the third point of suspension for the model. Hopefully, this three-point suspension would replicate the flexible chassis that made the Standard American such a successful design in those early days of American railroading.




I had to do some significant body work for this project. Although the frame had plenty of space for the motor and gear box in the middle, I had to mill the body to create space above, to compensate for the broader frame.


The General originally had ankle rails, a walkway that suspended from the cab and boiler and went along the locomotive, mounting outside of the drivers. Since the model represented the later walkways that went along the boiler and mounted above the drivers, I cut them off as part of the modification, filing the area up to the casting line [8].

I applied a new stack and new domes, created ankle rails from brass fretwire and shaped brass to cover the gaping hole in the smokebox. I used NWSL P:87 wheels for the lead truck and, since I could find no drivers of P:87 profile, I went for P4 drivers from the Alan Gibson Workshop (www.alangibsonworkshop.com/Catalogue.pdf) instead.

For the motion, I retained the Mantua cylinders, slide bars, and crosshead. The Mantua original does not have piston rods, and I can live with this compromise because the ankle rails would hide them anyway [9].



8. After significant body work, I was ready to begin reassembly.




9. I shaped a piece of brass and epoxied it in place to fill the gaping hole in the firebox. I have soldered the fenders to the firebox, and the boiler fittings and ankle rails are in place. Ankle rails are literally a footboard that appear to hang off the boiler and cab, linking the cab and pilot.

Reproducing the Stephenson link motion required some serious research, which gave me an excuse to visit the B&O Railroad Museum at Baltimore to study the William Mason, a contemporary of the General. I took photos and made my best effort to replicate the motion on the model [10, 11, 12].


Finally, because the tender no longer had a motor inside, and because it represented a coal load rather than the wood load of the prototype, I decided to cut out the top and build a new one from brass. The tender was a single casting of zamak alloy, which proved exceedingly difficult to work with [8]. With an abundance of the three Ps. (patience, perseverance, and profanity), I was able to remove the top of the tender and get to the easy part of creating a new top, a U-shaped tank, and other details from brass [13].

With the details in place, I was ready to give the model a base coat of color. I used red for the wheels and the pilot, "Russian Iron" for the boiler, green for the cab sides and other details, and light brown for the tender interior. The ankle rails and other details are painted to represent bare metal [14].





10. B&O No. 25, William Mason, on display at the Baltimore Railroad Museum, is a contemporary Standard American that provided an opportunity for me to photograph some details. Because the William Mason is on display on the turntable in the center of the roundhouse, I could examine the arrangements around the cylinders at close quarters and take all the photos I needed.



11. The cylinders, showing the Stephenson valve gear and the pump to feed the boiler.



12. A closeup shows the equivalent area on Roswell.



13. The rebuilt tender matches the prototype much better. The water filler is a spare white metal casting, and I constructed a pair of toolboxes out of scrap brass.





14. Roswell now has a base coat of color.



15. The Roswell is complete with paint, decals, and light weathering.

I always enjoy seeing the transformation that the addition of pinstriping makes to a loco. Since it does not accurately represent The General, I named it the Roswell instead, using letters from alternative names in the decal set.

I also applied a coat of satin finish and a very light dusting of weathering. This is a selective application of Micromatte, a wax dullcoating agent, which I thinned with windshield washer fluid and lightly tinted – black on the topsides and brown/earth on the wheels and running gear. Locomotives in those days were kept clean, but inevitably showed the signs of being in traffic.

THE CAMEO LAYOUT

Cameo layouts are highly compact, fully operational, self-contained scenes that are designed for easy transport in a compact car to train shows. Designing the box for the cameo layout was the next part of this project.

At a train show, the operator would sit at the front and to the left of the scene, so the turnout controls and throttle connection needed to be in the lower left hand corner of the box. Staging would also be behind the operator for easy access.

I began with a 2'x4' sheet of 2"-thick insulation foam for the base. Using Liquid Nails adhesive, I attached plywood sides and a back to the foam base to create a box 2' tall. The front wall would be a cutout resembling a television screen, but I left that off until I had the layout scenery completed, using a piece of 3/4"-square molding to span the front instead, and provide stability [16].



16. This is the cameo layout box under construction.




I opted for LED strip lighting for the layout. I rigged it loosely in place on the ¾" molding during construction to help judge the scenery colors. I determined that where brilliant white produced an effect like a "wet Sunday in winter," a yellower tone was more successful in conveying a sense of a "scorching summer day in Georgia."

For staging, I used a 16" medical transfer disc, designed to enable an individual of limited mobility to maneuver into a car. Its hard rubbery plastic surface and smooth-running bearing made it an ideal staging turntable. With two curved tracks, I could use it to accommodate and turn around two full trains with one locomotive and two cars each [17].

TRACK

I drew the track plans on Templot, a track and layout design software package. I worked out the design from data I found on Dave Bright's website, Confederate Railroads




17. The complete staging yard is a turntable that can accommodate and turn two full trains.


(www.csa-railroads.com). The site is a wealth of information, maps, and images.

The description of a "Mile of Southern Track" suggests that ties would have been 2' 3" between centers and 10' long. This gives the impression of quite close spacing, not only from the broader gauge but also from longer ties.

I built a short section of test track to see what it would look like using plywood ties. I soldered code 40 rail to copper rivets that I installed in my ties for the test [18, 19].



18. A short section of test track to see what the tie spacing would look like. Note the piece of standard track on the left for comparison.



19. An end-on view, showing the effect of code 40 rail and P:87 wheels.




The trackwork owes a great deal to one of the members of a local model railroading club I belong to. Tony Gomersall effectively designed a completely new gauge to P:87 standards. He not only worked out all the required clearances (recognizing that wheels will be to P4 standards), but he also designed the gauges and templates to go with it. I am extremely grateful to him for his help [20].

Tony built all the turnouts for my layout, including a three-way, stub turnout (amongst other things) – using code 40 rail. The three-way requires only the one set of moving parts – it's just that they have to stop in three different positions [21]. I set up a simple system of wire-in-tube linkages to control the turnouts.



20. Tony Gomersall made the series of gauges essential for hand-laying track. On the left, a mint gauge for checking the gauge of the track. The length of the block will ensure a small amount of gauge widening on curves. In the center is a roller gauge, with additional grooves to align check rails on turnouts. On the right is a back-to-back gauge to check the gauge of wheel sets.



21. Tony built this three-way turnout using PCB ties to hold everything together and cosmetic wooden ties between.

The scene

The raison d'être for the fictitious railroad is the real Roswell Mill, a water-powered complex built in the valley of a tributary of the Chattahoochee River. The mill was a major producer of textiles and clothing, including confederate uniforms, and as such was a target in Sherman's Raid. Surviving buildings are brick, and there are brick-built workers' houses from an early stage of the development [23].

I did not design my cameo to be a close replica of the Roswell Mills, though I constructed the scene with a combination of brick mill buildings and timber outbuildings. I designed the mill to be situated in a valley somewhat shallower than the prototype [24].






22. An aerial view of the track plan.

23. You can get an historically accurate drawing of Roswell Mill from the Roswell Historical society (link below). In the drawing, the river is to the right, with the brick-built mill buildings and the steep slopes to the valley on the left. Today, trees have grown back over the whole area, and it is surrounded by the town of Roswell.

Link:

[roswellhistoricalsociety.pas
perfectonline.com/photo/
61595059-709B-45E6-
8E2E-842274248170](http://roswellhistoricalsociety.pas.perfectonline.com/photo/61595059-709B-45E6-8E2E-842274248170)



24. My cameo version is not a close replica of the scene, but there is a brick mill with timber outbuildings, a rather shallower valley, and the critical addition of a railroad – which had been carelessly omitted from the prototype. The front of the cameo has been installed and painted a pale gray. The three black patches on the far left are Velcro strips for holding a handheld throttle.



I downloaded simple, free, card-built structures to use for the wooden buildings in the scene. Abraham Lincoln's family home provides one, and a wooden barn of German origin provides the other.

I used two brick-building cardstock kits to represent the main factory buildings. One is a single-story shed from Germany. I placed it at the rear of the scene to represent a nondescript industrial store.

For the main structure, I used an OO scale Scalescenes factory that I scaled to HO scale for printing. I printed a couple of copies and modified the design by cutting away sections with a craft knife to reassemble a more interesting profile for the available space.

For the interior of the building, I composited a scene from old images of cotton mills. You do not see much through the windows, but it does give the impression of something inside.

The model



25. The view along the layout from the entrance to the staging yard shows the effect of the code 40 rail and broad gauge track. The siding on the left is laid with strap rail – flat metal strip laid directly on timber longitudinal bearers.



26. The yard with the mill in the background. The Roswell is switching freight cars. I still have not worked out how to make a coupler for the front of the locomotive.



27. The cabins at the left hand side of the layout, to balance the factory at the right. The tree has its uses for providing shade!



Rolling stock

US rolling stock at this period tended to stay close to its home system. However, I concluded that the appearance of GRR cars on the W&A would be plausible, so I lettered two for GRR. The network in the Southern states was pretty thin, with none of the inter-connectivity that developed quite quickly in the UK and also probably in New England [28].

In 1860, knuckle couplers had not yet been invented, and the US standard was the link and pin, which does not lend itself to automatic coupling!

For the model, I wondered whether it would be possible to fabricate something along the lines of the Alex Jackson coupling, which I use on my British models. I wanted to see whether it would provide an acceptable visual appearance, but also allow automatic coupling and uncoupling [29, 30, 31].

I haven't been able to display my layout yet, and no shows are on schedule because of COVID, but the project has proven most satisfying nevertheless. I am deeply indebted to the American Civil War Rail Road Historical Society (ACWRRHS), whose members have shown enormous patience with a



28. The entire selection of rolling stock, made up from kits by BTS and Alkem, mostly built with 3D-printed trucks.

newcomer who has been learning the basics about American railroading and the history of the period. I have never actually met any of the members face-to-face but the e-group and Zoom conversations have enabled this layout to happen. ☑



29. A trial version of the Alex Jackson coupling.



30. I formed the couplers from guitar string bent to shape in a jig. In UK practice, the car buffers maintain a distance when the vehicle is being propelled for uncoupling. I had to fashion a center buffer to represent the casting of the link-and-pin coupler, which is shown here still unpainted. To uncouple, a magnet or electromagnet buried in the track deflects the coupling downwards.





31. The coupling wire pivots in a short piece of small tubing, soldered to a brass plate and attached to the body of the vehicles above the truck. The counterweight has space to swing upward between the wooden underframes.

★★★★★
RATE THIS ARTICLE

ERIC GATES



Eric is a retired government servant, who lives near Bristol in England. He is a lifelong model railroader, who normally models the London, Brighton and South Coast Railway in the 1870s and to 4mm scale. The diversion to a US model of roughly the same period was an interesting

step out of the comfort zone! Eric and his family lived in Virginia for three years in the 1980s, when Eric was a member of the Northern Virginia Model Railroaders. ■



SUBSCRIBE

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

Stone structures



MRH Running Extra | May 2021

JAMES EAGER SHOWS HOW TO
CAST YOUR OWN SCRATCHBUILT
BUILDINGS USING THE LINKA
SYSTEM ...

BACK IN THE EARLY 1980s, I discovered a modeling product called the Linka building system of rubber and plastic molds used with a plaster-like casting material mixed with water. The molds were in HO scale, or very close to it, which suited me fine. At the time, I acquired a full set.

I found that the molds produced nice stone and brick, though the wood molds were unsatisfactory. The molds created small pieces of walls of several variations, including some blank



STONE STRUCTURES | 2

walls, some with windows, some angled, and so forth. Simply choose the right molds to build the structure you want.

Side-to-side, the pieces fit together tongue-and-groove, but the top-to-bottom fit is straight. The original kit came with a special glue, but I quickly learned that white glue worked just as well.

I first used the molds to build stone retaining walls on a module to line a river underneath bridges. That worked out very well. After a few years in storage, I brought the molds out for another project, this time an old stone country church [1].

Further searching on the internet even found an assembly plan for a similar church model built with the Linka system! Now we are getting somewhere.

By the time I started on this project, the original Linka company had ceased doing business, but an online community of Linka modelers (www.linkaonline.co.uk) continues the system. In addition to selling the old Linka molds, the group creates and sells new ones, as well as building plans.

I started with the Village Church plan, available online here: (www.linkaonline.co.uk/uploads/2/4/1/5/24159258/village_church.pdf). The plan has a handy list of which molds



1. Two examples of stone churches I found online to inspire my project.



SUBSCRIBE

[INDEX](#)


[TABLE OF CONTENTS](#)

MRHMAG.COM


[INDEX](#)

[TABLE OF CONTENTS](#)


and how many castings of each to use [2]. From there, it was a process of mixing the plaster with water (25 ml plaster to 15ml of water), pouring the mixture into the molds, leveling and smoothing the back, and allowing to set. I repeated the process as needed for each casting [3, 4].



2. Some of the molds required for the project.



3. Pouring the plaster into the molds.



4. Smoothing plaster after pouring.

I used the church plan as a starting point, but modified it to remove the large arched window on the end, and substitute a large round window. I began with a plain wall casting, and drew two circles with a compass. The inner circle represented the outline for the window, and the space between the inner and outer circles represented the frame.

I drilled a starter hole in the center of the circle. I then used an X-Acto knife to carve and break away material until I reached the inner ring. I wound up breaking the wall, but I glued it back together.

I used my Dremel motor tool to grind away the stone face between the inner and outer circles to create a frame for the window. For the window itself, I found a photo of a round, stained glass window online, and printed it [5].

The other modifications I made to the plan were unintentional. I omitted to mold the bottom two layers of stone for the entryway. I wound up leaving that lower segment and the entry steps off the model.



STONE STRUCTURES | 5

The mold of the steeple was great, and was rather pointy, until the tip ran into my work light. Drat! I rounded it off with my Dremel tool.

I wanted to use photos of real stained glass windows on the model, and I found about two dozen online. I chose the most usable ones and used Photoshop to adjust the size to fit the model.

I tried three different methods to print and install the windows, but the first two were unsuccessful. Printing the file directly onto acetate didn't work because it smeared too easily when I touched it. My second attempt, – spraying the acetate with clear lacquer – caused the ink to bead-up and created a mess.

For my third attempt, I printed the window on regular white paper, then glued that to the acetate. This worked well. As an added bonus, the paper muted the bright bulbs I used to light the interior of the building [6, 7].



5. The round stained glass window.

STONE STRUCTURES | 6



6. Right side of the church.



7. Left side of the church.



SUBSCRIBE

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

I made my first attempt at roofing the structure using the shingle tile the plan called for. The seams were awful. I substituted a wood base and pre-made shingles from Northeastern Scale Lumber instead (www.northeasternscalelumber.com).

Finally, even with the best of care, the Linka system shows seams. The better you are, the fewer, but it is just hard to get rid of them all. I hid mine with ivy.

To complete the scene, I used a wedding party from Preisser, and added a 1959 Cadillac Eldorado as their wedding car. I used dried goldenrod to create a tree for the scene. Now to find the perfect spot on my eventual train layout [8].

The beauty of the Linka system is that you can use them for just about anything. As mentioned, my first project was a



8. Get those wedding photos!



9. I built this suburban station for a friend from some of the same molds I used for the church. With the versatility of the Linka system, the only limit is your imagination.

retaining wall. My next project, beginning with spare parts from the church – I always make a few extra castings because plaster can be fragile – was a train station, but that's another story [9]. ✓

JAMES EAGER



James (who passed away June 3, 2016) had been a programmer and database administrator for several major corporations.

He and his brother each received trainsets which led to a father and sons' layout in the basement, a Model Railroading Merit Badge, and a long-term interest in model railroading.

In 1997, as part of a Jacksonville model railroad club, one of his structures was shown in a TV commercial for the Ronald McDonald House Christmas charity layout at the mall.

James had a long-time interest in the Illinois Central, along with the B&O and ATSF. ■

★★★★★
RATE THIS ARTICLE

THE AH-HAH MOMENT

column



MRH Running Extra | May 2021

JOE FUGATE PROVIDES SAFER AIRBRUSH
CLEANING SOLVENTS ...



THE DEBATE CONTINUES TO RAGE ONLINE ABOUT WHAT'S THE BEST AIRBRUSH CLEANING SOLVENT to use that's both safe for you to breathe and will not harm your airbrush.

Some swear by spraying Windex window cleaner through the airbrush at the end of the session, since it's widely available and relatively cheap. But others warn ammonia is bad for the seals and O rings in your airbrush.

There's also some concern that ammonia corrodes brass, and under that nice chrome plating of your airbrush lies a core of brass. If any micro-fissures exist in the plating, there's a chance the ammonia may find them and begin attacking the brass.

I don't know if that's true since the concentration of ammonia in Windex is fairly low. But a couple online sources I trust recommend against using Windex with ammonia for airbrush cleaning. See: [the Airbrush Guru](#) and [Don's Airbrush tips](#).

Safer, reasonably economical airbrush cleaning solvent alternatives exist, so why chance it? Just use the safer alternatives instead – so let's review them in this *Ah-Hah* moment.

First, there's good ol' IPA [1] or isopropyl alcohol (91%). Unfortunately, thanks to the pandemic, IPA has become somewhat pricey. Plus IPA does have a strong odor when sprayed.

To get a shopping list for this article, visit the *MRH* website at this link: mrhmag.com/magazine/running-extra/2021-05/ah-hah-moment#shopping

THE AH-HAH MOMENT | 2



1. One reasonably safe alternative for cleaning your airbrush at the end of a session is to spray 91% isopropyl alcohol through it.



2. An even better airbrush cleaner that's environmentally safe but also quite effective is Simple Green cleaner.



3. If you want an affordable cleaner especially designed for cleaning your airbrush, Klean Strip Paint Sprayer cleaner. It's economical and formulated to be safe to spray.

Another inexpensive alternative I like is *Simple Green*. It's environmentally friendly, yet works great as a final cleaner you spray through your airbrush.

Another product specifically made for cleaning an airbrush is *Klean Strip Sprayer Cleaner*.

Here's what one reviews said:

"After each spray session I fill the paint cups with cleaner and shoot it through ... no strong stinky after-spray and it cleans just fine! It does exactly what it's supposed to do and doesn't make me worry about flammability and odor hazards while I do it. A gallon will last a *long* time."

If the paint in your airbrush is fresh and not dried for hours, these cleaners should do the trick. Next month: getting out stubborn dried paint! ☑



SUBSCRIBE

[INDEX](#)

[TABLE OF CONTENTS](#)


MRHMAG.COM

[INDEX](#)

[TABLE OF CONTENTS](#)

Bonus section!

Here are all the pages from
the May issue of
*Model Railroad
Hobbyist* magazine
as well!



ALSO:

- Double crossover wiring
- Model a loading area
- Building a small N scale layout
- Modeling highway lines
- ... and more inside!



Victor Roseman on

**Modeling
urban
structures**

► READ NOW



[SUBSCRIBE](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

WIDE EDITION

Hard-coded facing pages PDF

[TABLE OF CONTENTS](#)

Now Available from



ATLAS HO AND N SCALE FORD F-100 PICKUP TRUCKS



Union Pacific

Products bearing the Union Pacific marks are made under trademark license from the Union Pacific Railroad Company.



Chicago & Northwestern



Canadian Pacific



Great Northern



Boston & Maine



Erie Lackawanna



Rock Island



British Columbia



Southern

PICK A FEW UP FOR YOUR LAYOUT!

[CLICK HERE!](#)

FOR MORE INFORMATION OR TO LOCATE A DEALER, PLEASE VISIT WWW.ATLASRR.COM.
ATLAS MODEL RAILROAD CO., INC. • 378 Florence Ave., Hillside, NJ 07205

STAFF

HAVING FUN WITH TRAINS

MRH

MODEL RAILROAD HOBBYIST

Model Railroad Hobbyist | May 2021 | #135



RATE THIS ISSUE

ISSN 2152-7423

Editorial Staff



Joe D. Fugate, Publisher and Editor



James Regier, Assistant Editor



Patty Fugate, Pasteup and Layout



Richard Bale, News and events



Jeff Shultz, News and events, Tech Assistant



Mike Dodd, Copy Editing

Advertising

Les Halmos, Account Manager
Jean-François Delisle, Marketing Assistant

Regular contributors

Eric Hansmann, Contributing editor
Jim Six, Limited Modeler column
Ken Patterson, Reporter-at-Large

Rotating Columnists

Jack Burgess, Getting Real column
Marty McGuirk, Getting Real column
Nick Muff, Getting Real column
Mike Rose, Getting Real column
Tony Thompson, Getting Real column

Rob Clark, Imagineering
Dave Meek, Imagineering
Ray Dunakin, Imagineering

Published for the glory of God. [What's this?](#)



REGISTER
(free)

[INDEX](#)


[TABLE OF CONTENTS](#)

MRHMAG.COM

[INDEX](#)

[TABLE OF CONTENTS](#)

MRH SPONSORS



Model Railroad Hobbyist | May 2021

A - L



acculites.com



railroadhobbyshow.com



archertransfers.com



www.atlasrr.com



bachmanntrains.com



berrethill.com/trains



blairline.com



coffmaneng.com



deluxematerials.co.uk



www.digitrax.com



drduino.com



dwarvin.com



esu.eu/en



handlaidtrack.com



iascaled.com



krmodels.ca



litchfieldstation.com

Vendors: Get your clickable logo on these pages ...

MRH SPONSORS | 2


M - Z



micro-trains.com



store.mrhmag.com



modeltrainitems.com



www.modelrectifier.com



handlaidtrack.com/mt-albert-scale-lumber



ncedcc.com



nmra2021.com



www.pwrs.ca/main.php



rapidotrains.com



ringengineering.com



roometteslighting.com



scaletrains.com



soundtraxx.com



sodigi.com



sbs4dcc.com



tamvalleydepot.com



trainfest.com



walthers.com



woodlandscenics.com

Looking for something? Check the MRH Marketplace!



Take me there!



Thinking of buying
or selling something?

click here

Looking to pay
minimal fees?

click here

ModelTrainItems.com

Photo posted on mrhmag.com by Bill Beverly



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

MODERN MOTIVE POWER

BNSF ET44 Tier 4
HO Scale GEVOs



HO Scale Preproduction Models Shown

PREORDER NOW
JULY ARRIVAL

BNSF

Also available in:



HO Scale Previous Run Shown



ScaleTrains.com, Inc.
7598 Highway 411
Benton, TN 37307
844-9TRAINS 844-987-2467
International 423-299-3689

Photography by Ken J Johnson

PUBLISHER'S MUSINGS



Model Railroad Hobbyist | May 2021

**JOE FUGATE ON MODELING
HIGHWAY ROAD MARKINGS ...**



IT'S SURPRISING HOW MANY DIMENSIONS OF COMMON THINGS CAN BE A MYSTERY. Recently someone on the MRH forum asked about the dimensions of the painted markings on highways.

Anybody care to guess what the answer is? (Those of you who already know the real answer, put your hands down.)

I kind of remembered the lines themselves tend to be about 6 inches wide, but I had to search the web to find the answer on the length and spacing of the dotted lines in the center.

There's a slight difference between highway markings in North America and those in the rest of the world. Since we focus on North American railroading in MRH, I'll just discuss North American highway marking standards.

History of prototype highway marking standards

Like many aspects of transportation technology, highway marking standards evolved throughout the 20th Century.

Early paved road centerlines first appeared around 1911, but publications clearly show paved road centerlines became common by the mid 1920s. However, there was no common standard yet.

✉ **REGISTER**
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

PUBLISHER'S MUSINGS | 2

The Manual on Uniform Traffic Control Devices (MUTCD), published in 1935, became the first real document to outline standards. This document not only dealt with road markings, but also with standardizing roadway signs, signals, and islands.

This initial manual recommended white for all lines, except calling for yellow double centerlines on multi-lane highways and no passing zones.

The US published the first major revision to the MUTCD during



1. Highway markings have changed through the years. Do you know the right size to make scale highway markings in your modeled era?

ADVERTISEMENT

**MICRO-
TRAINS®
LINE**

UNION PACIFIC® 3-PACK

N
SCALE 1:160

NEW ALTERNATE ROOF WITH UP® SPECIFIC DETAIL



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

WALTHERS MAINLINE®

TOUGH, STRONG, DEPENDABLE.

New SW7 and NW2 Locomotives
now available at walters.com



WALTHERS® Order yours today!

© 2021 Wm. K. Walther, Inc.

MRHMAG.COM

[INDEX](#)

[TABLE OF CONTENTS](#)

World War II in 1942. Essentially, this edition of the manual only made changes necessary to support traffic during wartime and postponed making any major revisions until after the war.

Most of the changes involved using different materials to deal with wartime shortages or to manage traffic control during blackout conditions.

The 1948 edition of the MUTCD involved a lot of debate and opinions from experience but not much real scientific study.

White continued to remain the main marking color, with yellow remaining the double-center-line color. This edition recommended against markings for pavement edge lines.

The road markings in the 1948 MUTCD: 4-6 inches wide, with dotted lines 15-foot long separated by a 25-foot gap. About half the states preferred to mark the center-line on concrete pavement with a black line instead of a white line.

Rocket Card Glue

WOW!

LEARN MORE



Clean, neat,
instant (like superglue)

'Born for cardstock modeling'

Available from your local
hobby store



CLICK TO BUY



Coming attractions!

Charlie Comstock


Bear Creek
& South
Jackson
layout
update



Joe Fugate

DCC
Decoded
topics

3 clinics



Geoff Bunza

Layout
animation
techniques

6 clinics



3 clinics
now filmed!

Bruce Chubb

Op Session
on the
Sunset
Valley



New!

Already filmed!

Rick Sutton

Photo-
realistic
modeling

6 clinics




3 clinics
now filmed!

Greg Baker

Realistic
scenery &
weathering

8 clinics



All 8 clinics
now filmed!



Special discount pricing available!

TRAINMASTERS.TV

Don't miss out on these videos! **CLICK NOW**



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

PUBLISHER'S MUSINGS | 4

For all the historical details, see this PDF:

ceprofs.civil.tamu.edu/ghawkins/markings%20color%20evolution.pdf

The US revised the MUTCD document in 1954, with the most significant change being to standardize the stop sign from yellow to red. The 1954 edition also specified using a reflective paint additive make the road markings more visible at night.

The 1961 edition of the MUTCD added new standards for freeways and for construction zones. This edition of the manual pushed hard for standardization and eliminated many previously permitted alternatives.

Most notably, the 1961 edition allowed the centerline color to be yellow as an alternative to white. It also ended the prohibition on pavement edge lines.

White could be used as lane lines, as well as for road edge lines and for stop lines, for crosswalk lines, and for warnings or symbols such as railroad crossing warning markings.

Centerlines remained 4-6 inches wide, while pavement edge lines should be 2-4 inches wide. The centerline length remained at 15 feet with the gaps at 25 feet.

The Federal Highway Administration took over the maintenance of the MUTCD with the publication of the 1971 edition. The 1971 edition finally *mandated* yellow center lines for lane markings separating opposing lanes of traffic. The 1971 edition specifies white lines only for separating lanes that flow the same direction, or for pavement edge lines.

It also mandated that the left pavement edge line for a set of lanes all going the same direction must be yellow.

The 1978 edition of the MUTCD changed the general dotted line dimensions to 10 feet long with a 30 foot gap. By the 1988 edition,



THE SHAY



The Shay locomotive was the most widely used geared steam locomotive. The locomotives were built to the patents of Ephraim Shay, who has been credited with the popularization of the concept of a geared steam locomotive. Although the design of Ephraim Shay's early locomotives differed from later ones, there is a clear line of development that joins all Shays. In 1884, they delivered the first 3-cylinder (Class B) Shay.

Class B: three cylinders, two trucks. Weight between 10 and 60 short tons (8.9 and 53.6 long tons; 9.1 and 54.4 t) tons.

Our rendition of The Shay will feature ESU LokSound V5 sound decoder. Cast Chassis, working external valve gear and drive shafts. Working directional lamps front and rear.

Limited production run

Expression of interest link now OPEN

DCC Ready \$299

DCC Fitted \$339

DCC Sound \$449

HO scale

Expected delivery Fall 2022
Easy pay 0% installment plan available

www.krmodels.ca

PUBLISHER'S MUSINGS | 5

the edge lines became mandatory except where engineering considerations made an edge line impossible.

In the early 2000s, most road marking traffic departments shifted from oil-based to acrylic paint to address concerns over exposure to VOC solvents.


Modeling highway markings

When it comes to modeling highway markings on our model roads, it all depends on what period you model.


We usually fit roads into the space between model structures, typically in shorter segments. It's rare to see a scene with a long stretch of highway more than a few feet long.

If you're modeling a time after 1980, the spacing changed from a 15-foot line and a 25-foot gap to a 10-foot line and a 30 foot gap. The standard also says you can make the lines and spacing shorter if you maintain the same line-gap relationship.


"Right and Splice Clamps"™



Quality Tools with Superior Versatility



Essential Tools for Great Modeling



Coffman Graphic Solutions
1500 River Circle, Richmond KY 40475

[Click Here](#)

Visit our new Website:
www.coffmaneng.com



NEW, LIMITED-RUN MICRO-TRAINS CARS

GE RAIL SERVICES (NAHX) 3-BAY CENTER FLOW COVERED HOPPER 4-PACK

COMING
JAN 2022



CLICK HERE FOR
NAHX HOPPER



4600 cu.ft., 100 tons, 57' 5" long with elongated hatches, painted light gray.

Two cars are lightly weathered and rusted, two are heavily rusted.

UNION PACIFIC (UP) "BUILDING AMERICA" 3-BAY COVERED HOPPER 4-PACK

COMING
FEB 2022



CLICK HERE FOR
UP HOPPER



4600 cu. ft. 3 Bay Centerflow Covered Hoppers, with trough hatches. 100 tons, 55' 5" long.

Painted yellow with Union Pacific herald on patch.


Pacific Western Rail Systems

LIMITED RUN OF MINIMUM 50 SETS-MADE EXCLUSIVELY FOR PWRS BY MICRO-TRAINS



2. One official standard for centerline markings says the lines can be 3-foot with 9-foot gaps. No passing zones use a solid yellow line. From the [2009 MUTCD, Chapter 9](#).

Figure 9C-2. Examples of Center Line Markings for Shared-Use Paths



One standard that works better on our all-too-short modeled highways can be found in chapter 9 and recommends a 3-foot line with 9-foot spacing [2].

No matter what, unless we have lots of space to model highways, prototype dotted line spacing looks odd if you plot it out [3]. I think one reason for that comes from the normal viewing angle we're used to seeing from when we look at a real road.

We typically see a roadway from a seated position inside a vehicle, which puts our viewpoint just a few feet above the road surface. That automatically compresses the dotted line to make the lines look much shorter and closer together.

We're just not used to seeing a highway from the typical helicopter viewpoint.



Load Up on What's New in N Scale Bethlehem Steel 100-Ton Three-Bay Hoppers - Available Now!

Bachmann's new Bethlehem Steel 100-Ton Three-Bay Hoppers are with you for the long haul to help complete your N scale freight jobs with ease. Modeled after their 1960s-era prototypes, they arrive in five different road names with a removable coal load included. Hop online to find your local hobby retailer and check out Bachmann's new rolling stock today!

Features include:

- Silver Series® rolling stock – fully assembled
- highly detailed painted bodies with precision graphics
- blackened, machined-metal wheels with RP25 contours
- magnetically operated E-Z Mate® couplers
- non-magnetic blackened brass axles with needle-point bearings, Celcon® trucks
- added weight for optimum tracking performance




UNION PACIFIC® #36255
Item No. 18751



CONRAIL #488506
Item No. 18752



NORFOLK SOUTHERN #145275
Item No. 18754



PENNSYLVANIA POWER & LIGHT #286
Item No. 18755



SHIPPING NOW!
MSRP \$47.00 each


Bachmann Industries, Inc. • 1400 East Erie Avenue • Philadelphia, PA 19124 USA • www.bachmanntrains.com

Click for more information.

LAST CALL FOR THE F59PH!



CLICK HERE



3. Another MUTCD standard calls for 2-foot lines with 6-foot spacing. Compared to the standard 10-foot line with 30-foot spacing, the shorter and tighter spacing does look better for modeling purposes. In fact, I recommend selective compression to a 3-foot line and 5-foot spacing for the best look.

We selectively compress other parts of our modeling, so why not likewise selectively compress highway markings? I see a 3-foot line with a 5-foot spacing to look the most natural for our selectively compressed model roads. See diagram [3]. ✓



Every little bit helps!




Registered MRH readers* get **another** 10% off with the coupon code here:

[click here](#)

**Try it.
It works!**

*Registering is free



**Reveal my
coupon code now!**



Have a great
Summer!

That's right, on top of our other sales and discounts, use this coupon code to get **YET ANOTHER 10% off!**



TMTV sale offers

[click here](#)



MRH Store sale offers

[click here](#)



LAST ISSUE RATINGS

Top rated articles in the [Apr 2020 issue](#) of *MRH* are:

- 4.7 Build a small N scale layout, part 1
- 4.7 Publishers Musings: Update on the forum migration
- 4.7 April 2021 news

Issue overall: **4.7**

Top rated articles in the [Apr 2020 issue](#) of *Running Extra* are:

- 4.7 Getting Real: Modeling Mt Vernon Radiator
- 4.7 Realistic tin roof modeling
- 4.6 Trenton Subdivision, inspiration for a layout

Issue overall: **4.9**

Rate the articles! Click the comments button on each article and select the star rating you think it deserves. ■

Get the latest Model Railroading News, Tips, Reviews & Opinions



Our iTunes feed has changed search for "Crew Call with Mike Rose" to receive the latest episodes!

www.themodelrailroadpodcast.com

Host:

Mike Rose: www.mrhobby.com

**Don't Miss our Monthly Interviews
& Product Announcements**



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

MRHMAG.COM

[INDEX](#)

[TABLE OF CONTENTS](#)

WHAT'S NEW on TMTV!

Non-members: Watch episodes for \$1.99 ea, become a member for unlimited access

Brought to
you by
MRH
MODEL RAILROAD HOBBYIST



Introduction to Arduinos



Superglue for cardstock



Easily clean paint off railheads



QAT: Managing DCC shorts



TRAINMASTERS.TV

Don't miss out on these videos! **CLICK NOW**



Best of the

MRH WEBSITE

THIS MONTH

Model Railroad Hobbyist | May 2021

Website
MRH
mrhmag.com

Compiled by **JOE FUGATE**



A new layout space!


It's always exciting to hear about someone getting a new layout space, and *MRH* forum member **JSET** (Alan Feldman) shows off his latest acquisition in this blog entry.

Visit the thread and have a look! This will be great fun to watch as the build out develops and Alan documents it for us.



View the full thread on the MRH website

► **MRH'S MONTHLY GREAT MODELER POSTS**



1. John Sackis 3D prints many of the details for his layout. Along the way, he has been exploring 3D printing in great depth.

3D printing layout details: hobby within a hobby

MRH forum member **Photo Bud** (John Sackis) has a long-running blog about his layout that started with a Timesaver and has been expanding ever since.

John has found 3D printing layout details becoming its own hobby-within-a-hobby for him as he refines his 3D printing knowledge and upgrades his 3D printer. For instance:

"I switched nozzles on my 3D printer from 0.4 mm to 0.2 mm for finer detail and it seems to have helped! Pop machine on left was printed with 0.4 mm diameter opening nozzle, the one on right and the Lara Croft were with 0.2 mm nozzle. Penny to show the size necessary for my HO train layout!"

Follow John's journey in his MRH forum blog.

[View the full thread on the MRH website](#)

INTRODUCING!
CHECK 'EM OUT

BOXCAR INTERIORS
for ATHEARN and ATLAS cars

Roomettes

Lasercut structures. Highway, storefront and billboard signs.

Neat ag customer for your railroad:
Farmers Fertilizer Supply

WHAT'S NEW?

Established 1993...
Blair Line

Where prototype modeling, operations & technology converge ...

Join us in Santa Clara for NMRA 2021. Key events include: Great Climax and more.

Replaced with virtual event ...
click to learn more!

Archer
FINE TRANSFERS
PROUDLY SERVING MODEL BUILDERS SINCE 1989

THE ORIGINAL
SURFACE DETAILS™

WE NOW HAVE MORE THAN 130 SHEETS OF RIVETS, LOUVERS, TREADPLATE, WELD SEAMS AND MORE CAST ONTO MICROSCALE CLEAR DECAL FILM

LOW SHIPPING:
DOMESTIC USA ORDERS \$2.80
INTERNATIONAL ORDERS \$9.95


CLICK HERE TO VISIT OUR WEBSITE!

Archer Fine Transfers 3D decals have revolutionized kitbashing and scratchbuilding. Putting rivets or other low-relief details like louvers or weld seams on your models is now as easy as applying decals.

Joe Fugate, Publisher/Editor Model Railroad Hobbyist

MADE IN THE USA

Archer Fine Transfers • PO Box 1277 • Youngsville, NC 27596 • USA (919) 570-1026 • info@archertransfers.com • archertransfers.com



2. Will Annand wants to control his turntables using an inexpensive Arduino microprocessor, so he asked the *MRH* forum members for help.

Arduino controlled turntables

Forum member **Will Annand** wants to explore using an Arduino to control his two layout turntables, so he's asking the *MRH* forum members for advice.

Already, several forum members have offered advice, with one of the most helpful posts from forum regular Prof Klyzlr, who has a reputation for thoroughly exploring a question with some great advice.

In this case, the Prof used MRH's own search box (what an idea, aye?) to search out and provide many superb past threads that delve into how to use an Arduino for this purpose. Nice to see the MRH forum is loaded with lots of great how-to advice like this. Just use the search box to mine that treasure!

Follow along to see how Will proceeds on this project.

[View the full thread on the MRH website](#)



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

ADVERTISEMENT

FAST TRACKS

Build your own trackwork easily, quickly, and affordably.



TRACK BUILDING SYSTEM



Introducing Diamond Line Crossing Kits




Building an accurate crossing has long been a challenge in our hobby.

Not anymore with Diamond Line Crossing Kits!

Fast Tracks Diamond Line Crossing Kits make the job of building a good looking, accurate crossing much simpler. Precision cast parts and matching laser cut ties work together to ensure quick construction. Each of the castings are designed to press into the laser cut ties, automatically locating all the parts and electrical isolation gaps. The parts are simply pressed and glued in place.

HO scale 90 degree versions are the first in what will be a large library of popular sizes


Single



Double



Quad



All Fast Tracks track fixtures and tools are NMRA compliant



Easy Ordering • Fast Delivery • Free Shipping*

*applies to North America only on orders over \$150.00 US

shop online 24/7

handlaidtrack.com

1-888-252-3895 service@fast-tracks.net



3. Randy Seiler documents the progress on his layout in his *MRH* blog. Here, you can see his progress scenicking a bridge abutment.

B&O/PC Cincinnati West - Construction

MRH forum member **RSeiler** (Randy Seiler) has a long-running blog documenting the progress on his B&O / Penn Central layout.

Randy has an interesting philosophy when it comes to scenery. He feels it should not take away from the trains, and he calls scenery done so as to not distract “operations pixie dust.”

“An operator going through a giant canyon is going to be distracted by barren canyon walls, causing the dreaded operations unimmersion we work hard to avoid. Covering it with [generic] foliage prevents operations unimmersion, and enhances the operating experience.”

Follow Randy’s blog on the *MRH* website. It’s great reading, full of useful learnings.

[View the full blog on the *MRH* website](#)

Latest *MRH* Weekly photo fun thread

Every week, a new Weekly Photo Fun thread appears. Here’s a recent sampling to show it’s not all just pretty pictures ...

[View the full thread on the *MRH* website](#)



4. The top photo from *MRH* forum member **p51** (Lee Bishop) hints at the WWII era of Lee’s narrow gauge layout.

To the right is a photo posted by **ssagrawal** (Siddharth) showing his latest benchwork progress thanks to advice from *MRH* forum members. Wonder what that strange dead-end cork curving off the the right is all about? Click on the photo to learn more.



★★★★★
RATE THIS ARTICLE

Get all these
layout tours for
just \$9.99

Ordinarily ...
1 week rental is
\$1.99 per video

Watch free samples >>

Pay just
9.99 94%
discount!


And get unlimited
access to all 80 layout
tours!

Get layout tours >>

(Or get a full access
membership and view all
these layouts + 500 more
videos ...)



www.trainmasters.tv



WHAT'S NEAT

column



Model Railroad Hobbyist | May 2021

KEN PATTERSON'S COLUMN THIS MONTH ...

- Creating a loading zone
- Working with low melting temp alloys



THIS MONTH KEN FINISHES UP THE SCENERY ON A MODULE showing how he uses concrete patch to make roads and loading zones, as well as demonstrating how to recreate track that is buried in dirt and grass. George Bogatiuk shares how he uses low melting temperature metals to add weight to locomotives and cars by filling unseen voids.



click to play video


PHOTOS AND VIDEO OF SUPERB MODELS

Burying track in scenery and creating a loading pad



1. Continuing work on a module featured in the September 2020 "What's Neat," Ken begins working on the scenery on the front half of the module by painting the ties shades of gray and black, which will give a weathered appearance when blended with the dirt.

Please include a phone number when emailing us if you need a reply!
(Just in case your spam filters eat our email response ...)



2. To build the road crossing, Ken uses HO scale wood ties, using plenty of wood glue to hold them in place.



3. Once the road and the road crossing dried, Ken got started on the loading area, liberally spreading the DAP Ready-mix Concrete Patch across the tracks and loading area. He first demonstrated this method of road construction in the September 2016 "What's Neat" video.



4. Ken wets the surface of the concrete patch using a spray bottle, and then uses a wide drywall knife to spread the pavement until smooth.

To get more MRH ad-funded pages, please click on the ads.



Also see the "What's neat this week" weekly video podcast!

**WATCH
NOW »**



5. After the pavement was dry, Ken sanded smooth any high spots and colored it with a wash of India ink and alcohol. By varying the amount of wash used, roads of different ages and maintenance levels can be modeled.

Did you see this article?



Sources of pre-wired LEDs, any color, any size

In **MRH** **RUNNING**
EXTRA

Get the May eBook now

click here



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)



6. Ken finished up the scenery by covering the surrounding area in backyard dirt topped with two shades of Woodland Scenics ground foam. The mainline tracks were ballasted, and finely ground limestone was used to create shoulders on the roads and loading area. Instead of ballast, the code 55 track leading to the loading area was covered in various green shades of static grass for a weedy effect. The entire area was then sprayed with scenic cement to hold everything in place.

Did you see this article?




Modeling 19th Century railroading

Get the May eBook now

← click here

In **MRH** **RUNNING** **EXTRA**

Did you see this article?



Unconventional benchwork methods that work

Get the May eBook now

← click here

In **MRH** **RUNNING** **EXTRA**



Also see the "What's neat this week" weekly video podcast!

WATCH NOW »



7. To clear the flangeways, Ken used a hacksaw blade he had cut down to six inches to cut through the scenery materials and concrete patch to the depth of the tie spikes. As seen in [6], this is sufficient clearance for the largest modern locomotive models to pass. It can also be seen how the track both disappears into the grass and appears embedded in the loading zone surface. Watch the video to see the whole process from start to finish.



DID YOU KNOW *MRH* REGISTERED READERS GET FREE BONUSES?

CLICK TO REGISTER NOW - IT'S FREE!



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

Using low-temp melting alloys to add weight to locos and rolling stock



8. George Bogatiuk of SoundTraxx demonstrates how using CerroBend-158 and CerroLow-117 low-temperature-melting alloys can be used to add significant amounts of weight to rolling stock without damaging the plastic.

Did you see this article?



No more ugly track cleaning cars

Get the May eBook now

← click here

In **MRH** **RUNNING** **EXTRA**



Also see the "What's neat this week" weekly video podcast!

WATCH NOW >>



9. CerroBend-158 and CerroLow-117 are alloys that contain Bismuth, Lead, Tin and Cadmium. Proper protective equipment should be used when working with them.

Tell your friends about MRH!

We depend on word-of-mouth to grow ... if you don't share us, we don't grow



REGISTER
(free)


[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)



10. Fuel tanks, such as this one from an Athearn GP40-2, often contain voids between the curved shape of the tank and the rectangular mount on the locomotive chassis.

Did you see this article?



A Brit models
1860s Georgia
railroading

In **MRH** **RUNNING**
EXTRA


Get the May eBook now

[click here](#)



Also see the "What's neat this week"
weekly video podcast!

**WATCH
NOW >>**



11. Here George shows how he uses an old soldering iron and the CerroBend-158, which melts at 158°F/70°C, to fill one side of the fuel tank shell. He recommends against using a soldering iron that is used for normal electronics work, since the CerroBend-158 might contain substances that would harm electrical connections.

**When talking to
hobby vendors,
please
remember to
mention MRH.**



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

Building a layout from the base to the finished product




12. The Cerrobend-158 flows into the curved shape without damaging the plastic, which melts at a much higher temperature. George warns against leaving models that have had weight added using low-melting-temperature alloys inside cars on hot days, as the temperature in a parked car can easily exceed the melting point of these metals.




Also see the “What’s neat this week” weekly video podcast!

**WATCH
NOW »**



13. The fuel tank weighs 1.2 ounces after adding the weight, significantly more than just the plastic shell. Since locomotive models can weigh less than a pound, especially if you have removed weight to make room for a speaker, every ounce counts toward improved traction and pulling power.



14. Next, George adds weight to an ExactRail hopper car using the CerroLow-117 alloy. It melts at 117°F/42°C, lower than some summertime temperatures in the United States.



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)



15. According to reviews, this hopper is about 1 ounce lighter than NMRA recommended practice, which is easy to make up if you model the hopper loaded, but more difficult for an empty hopper.



16. Using his old soldering iron, George shows how he melts the CerroLow-117 alloy into the small voids between the hopper bays, where they will not be visible from the side or top.




Also see the “What’s neat this week” weekly video podcast!

**WATCH
NOW »**



17. Here George shows where he has added the CerroLow-117, with no damage to the plastic.



18. Adding a bit of paint disguises the metal, and weathering will hide it even more.



REGISTER
(free)


[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)



19. George also used the CerroLow-117 to add weight to the ends of the coal load for the model. Care must be taken when adding weight here, as too much weight can make the car tippy by raising the center of gravity too much.




20. George added 1.8 ounces of CerroLow-117 to this hopper. See the video for George's entire presentation.



RATE THIS ARTICLE


from the
**Model Railroad
Hobbyist Store**




Available now

★★★★★ 5/5
"These books are remarkable and very well done."

- James S.



Available now



Coming 2022

Get now and save - special pre-summer pricing

PAPERBACK BOOKS: FREE SHIPPING US - 50% OFF SHIPPING FOREIGN

eBook download
or
Paperback book

Make it run like a
Dream



Complete Train Control

The next Evolution in Complete Train Control®

- Premium Advanced 5/8 Amp Starter Sets.
- Throttles include a Color 2.4" LCD Screen.
- Starter sets are available as standard tethered or duplex radio.
- The system features a DCS210+ Advanced Command Station, DT602 series throttle, and includes a power supply to make getting started easier than ever.
- The DT602 series throttles can be purchased separately from the Starter Set.

Find out more @ www.digitrax.com



of Starter Sets



Evolution Express (shown) | \$460 MSRP

Standard Set Includes: DCS210+ Advanced Command Station, DT602 Super Throttle with Color Screen, UP5 Universal Panel, PS615 power supply, and a PS615 power supply.

Evolution Express Duplex | \$645 MSRP

Duplex Set Includes: DCS210+ Advanced Command Station, DT602D Super Duplex Throttle with Color Screen, UR93 Universal Panel, and a PS615 power supply.



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

MRHMAG.COM

[INDEX](#)

[TABLE OF CONTENTS](#)




- NCE
- Digitrax
- SoundTraxx
- Speakers
- Train Control Systems
- ESU LokSound
- Tam Valley Depot

623-298-7355

www.LitchfieldStation.com
sales@litchfieldstation.com

Double crossover wiring



Electrical
Impulses

G.T. GALYON ON HOW TO
WIRE A DOUBLE CROSSOVER
FOR RELIABLE OPERATION ...

Model Railroad Hobbyist | May | 2021

IF YOU CAN, I advise avoiding complicated track configurations such as double crossovers, double slip switches, and three-way switches. A single crossover is much simpler to install reliably, and will be less derailment-prone. However, you may need such track configurations to save space.

In this article, I describe my experiences with Shinohara HO scale double crossovers. You should be able to adapt what I present to any brand of double crossover, since the principles are the same.



DOUBLE CROSSOVER WIRING | 2

DOUBLE CROSSOVER OVERVIEW

Shinohara produced HO scale track under their own brand, and also branded for Walthers and other vendors. They produced HO scale double crossovers in codes 70, 83, and 100, with prices ranging between \$60-80 dollars.

Although Shinohara is no longer in business, you can still find Shinohara track for sale on eBay and at model railroading swap meets.

A second option is to build a double crossover from a kit. Fast Tracks sells such kits for a variety of rail sizes, and their website offers wiring strategies (www.handlaidtrack.com). Building these double crossover kits is not for novices, but you can buy them built-to-order.

A third option is to cobble together a double crossover from four individual turnouts and one suitable diamond crossing. Getting these crossovers to fit on 2" centers – standard spacing for parallel track in HO scale – requires some alteration to the components.

Melvin Perry has a web tutorial showing how to use Atlas switches and a diamond crossing to create a double crossover on 2" centers (melvineperry.blogspot.com/2012/06/june-25-2012-my-double-crossover.html).

Shinohara double crossovers work reliably out of the box if installed properly – with all surrounding trackage perfectly in gauge and flat.

Electrical shorts can be a problem as engines traverse Shinohara crossovers, though in DC operation, engines tend to roll through shorts as long as the engine is moving fast enough.

Reliability can depend on crossover angle and size. I find 80-foot passenger cars go through the Shinohara #6 double crossovers just fine, as well as all six-axle diesels I have tested. However, some equipment may have trouble with a tighter #4 double crossover.

ADVERTISEMENT

END OF TRAIN DEVICE

NEW SAFETY GREEN



Patented Technology - US Patent 7,549,609

**Bright Red
Flashing Light!**

**Installs in minutes!
No freight car
modification required!**

Does not affect Load!

↓ Car without Load ↓



↓ Car with Load ↓



**Click Here to
Learn More**

**RE RING
ENGINEERING**

ADVERTISEMENT

Great control in a tiny package




**Original
Touch Toggles**

- Touch Toggle™ plug in controls
- Bright clear indication
- Easy setup
- Flexible system

Stall Motors, Twin-coils,
Power, and Servos

Now for Tam Valley Depot
and MRservo too!



Made in the USA

What will they think of next?


www.berretthillshop.com

A CLOSER LOOK


The old-version Shinohara code 70 and 100 double crossovers have two metal crossbars across the point rails, which makes the point rails have the same polarity [1]. The open point rail is always opposite polarity to its adjacent stock rail.

Metal wheels may bridge the 0.060" gap between point and stock rail, causing shorts, making these old-versions DCC-unfriendly. In practice, I have not frequently encountered such shorts, even with long-wheel-base steam engines, six-axle diesels, and a miscellany of engine types with large flanges, such as older Rivarossi.

Significant design changes for Shinohara's new-version code 100 double crossover increased the stock and point rail gap to 0.095" and made the point rail transition curves more gradual



1. Shinohara old version double crossover point and closure rails.



2. Shinohara new version code 100 double crossover-point and stock rails.

[2]. This significantly decreased the potential for wheels to bridge the gap between stock and point rails and thus reduced the potential for shorts.

The design is still "DCC-unfriendly" because of a single crossbar, but I have yet to encounter any point-to-stock-rail shorting with the new-version double crossovers, even with the infamous Rivarossi pizza-cutter flanges or older Athearn sintered wheels.

[Using switch machine contacts to toggle frog and closure-point assembly polarity can cause shorts with slow-motion switch machines – the contacts can change polarity before the points have moved. -ed.]

Figures [3] and [4] show diamond crossings for old- and new-version Shinohara code 100 double crossovers. I call the

upper/lower converging rails K-rails (KU and KL). I call the left/right-hand converging rails the X-rails (XL and XR).


Though the converging X-rails are isolated from the X-crossing and from each other, the rails run continuous across the crossing, with one rail running underneath the other. The converging K crossings rails/guard rails are not continuous across the gap.

At a first glance, the old- and new-version crossings appear identical, but testing reveals important differences that may not meet the eye. Consider the red square and circles over the left-hand X-crossing in [3] and [4]. The squares are over the X-shaped plastic insulation separating the two convergent rails, and the circles mark the points of convergence for the X-rails.


“The new-version double crossover’s improved insulation ... has virtually eliminated shorting.”

The central part (the square) shows where all X-crossing shorts occur. The new-version double crossover’s improved insulation in the central part of the X-crossings has virtually eliminated shorting. I have yet to see X-crossing shorts on the new-version Shinohara code 100 crossovers.

Regardless of version, K-crossings on Shinohara code 100 double crossovers short-out consistently if you only set one of two diverging turnouts. I have had no K-crossing shorts when I have both diverging turnouts set. Before going any further, let’s digress and take a more detailed look at how K crossings work to understand what is going on.




3. Old-version Shinohara code 100 double crossover. The two middle rectangles denote the K rails, and the circles show the X-rails on left frog, and the square shows the plastic insulation point on the frog. The right frog, although not marked, matches the left frog.




4. New-version Shinohara code 100 double crossover. The new design significantly enhances the insulation, represented by the circles on either side of the square to virtually eliminate X-crossing shorts.

DOUBLE CROSSOVER WIRING | 7

If you set only one diverging and leave the other three turnouts in the “through” position, the K crossing converging rails will have polarities – phases is a more correct term in the case of DCC – as shown in [5]. If you simultaneously set both divergent routes, the convergent rails will be at the same polarity (either red or blue) as shown in [6].



5. K-crossing polarity schematic with one divergent route set. The wheel (in yellow) will cause a short as it makes contact between C and D.



6. K-Crossing polarity schematic with two divergent routes set. Since all polarities are the same, the wheel has no opportunity to cause a short.



Southern Digital

WWW.SODIGI.COM

Celebrating 28 Years serving you

All New Items from **Digifrax**
Complete Train Control



Evolution Express DuplexRadio
List \$645, Your Price \$516



Evolution Express
List \$460, Your Price \$365



DT602D Radio Throttle
List \$260
Your Price \$208



UT6D Radio Utility Throttle
List \$170
Your Price \$136



DT602 Super Throttle
List \$195
Your Price \$156



UT6 Utility Throttle
List \$105
Your Price \$84



UR93 Duplex Receiver
List \$125
Your Price \$99.95



BD4N Block Detector
List \$36
Your Price \$29



BXPA1 Auto Reverser
List \$49
Your Price \$39



Ni-MH Battery for
DT602 or UT6
List \$12
Your Price \$9.60

DCC Conversions, Service & Support

E-mail: sales@sodigi.com (770) 929-1888



[6] is a K crossing schematic for the case where both divergent routes are set simultaneously and all four convergent rail/guard rails are at the same polarity. You cannot get red-blue shorting with this route configuration.


WALTHER'S SHINOHARA CODE 83 DOUBLE CROSSOVER

The code 83 Walthers (Shinohara) double crossover is DCC-friendly because of clever internal wiring [7]. You can install the Walthers code 83 double crossover with just point-to-stock rail switching, and it will run smoothly without shorting.

You should provide some positive retention to the switch rod to maintain adequate contact pressure for continuity between the point and stock rails.

The code 83 turnout frogs are dead, with isolation gaps on either side. I have not encountered any dead frog problems, but you can provide power to the isolated frogs if you wish.

Shinohara has removed all metal crossbars and hardwired the point rails to their adjacent stock rails to eliminate any point-to-stock rail shorting. I can recommend the code 83 Walthers (Shinohara) double crossover, but there are couple of caveats.



7. Walthers Code 83 Double Crossover Wiring Schematic-jumpers shown.

First, the code 83 has internal rail jumpers built into the crossover that can sometimes lose their electrical contact to the rails.

Four of five crossovers delivered to my club and its members – the Olde Newburgh Model RR Club in Walden, NY – were in good order. The fifth, for which all jumpers had failed on one side, arrived without a box and had likely been mishandled in transportation or previous use.

My advice is that you immediately test your code 83 double crossover and return it if you find any broken jumper wires. You can repair broken jumpers on the code 83, but I would not recommend it unless you have sufficient soldering experience.

Second, flangeway binding and pinching can be an issue. The NMRA specifications for flangeway widths in HO have a tolerance range between 0.040"-0.050". Shinohara code 70, 83, and 100 crossovers are right in the middle of this tolerance range, testing at 0.043"-0.045"

RP-25 (either code 88 or code 110) wheel sets will make it through the code 83 double crossover, but there is some wobble, probably because of flangeway tightness through the frogs, combined with rail curvatures on the divergent route rails as they approach the frogs.

The "wobble" is minimal with most wheel sets; if your locomotive roster gets through the C83 crossover acceptably, then do nothing.

I have encountered binding issues with some older locomotives passing through the code 83, including an Athearn SW1500, a Bowser K-4 Pacific, and a Rivarossi 2-8-4.

I was able to improve the running performance by burnishing the sides of the rails and plastic insulation, and widening the flangeways by removing material from the rail/plastic insulation sides.


DOUBLE CROSSOVER WIRING | 10

To polish the plastic insulation flangeways, I first slide a styrene strip (0.040" to 0.045" thick) through the flangeways several times until it glides smoothly.

Then I slide a Dremel abrasive disk about 0.043" thick through the flangeways. I use my thinnest flat-sided file (0.045" thick) to widen the flanges near the turnout frogs to facilitate long-wheelbase steam engines and six-axle diesels.

SHINOHARA CODE 100 DOUBLE CROSSOVER WIRING

Let's take a moment to go over some schematics for Shinohara crossovers. [8] is for a Shinohara code 100 double crossover with all points at neutral, or mid-throw between straight and



8. This is a generic schematic for Shinohara code 100 double crossover schematic with point rails neutral. I have circled the potential electrical trouble spots.

Red and blue rails denote polarities. Green rails are switchable to either red or blue polarity, depending on the turnout position.

The gaps that Shinohara builds into the design are at points I, KU, KL, and J. Though some wiring schematics eliminate the gaps at I and J, I would caution against it because switch machine contacts work on a delay. Without I and J gaps, this delay may cause a short circuit during the switching cycle.

Easy Tsunami² Upgrade Sound Value Steam Models!

Get a quick decoder upgrade for your Bachmann HO Sound Value steam models with our new Tsunami² TSU-BH2.

The TSU-BH2 offers 8 function outputs and an easy install. Simply replace the Sound Value decoder and enjoy all of the Tsunami² features you love!

This decoder is designed to replace the factory board in the following HO Bachmann Sound Value Steam Models: 2-6-0, 2-8-0, 4-6-2, 4-8-4 Class J and GS4.

Shop at **SOUNDTRAXX.com**
or your local retailer today!




Did you know
there's an
MRH/RE index
available?

CLICK TO FIND OUT MORE


DOUBLE CROSSOVER WIRING | 11

diverging. You would rarely have your turnouts in this position deliberately, but it illustrates how the points polarize the portions of the double crossover in green.

For comparison, let's look at the same as-manufactured Shinohara code 100 double crossover with two turnouts aligned to a diverging route [9], or with all four turnouts set to diverging [10].




9. Shinohara code 100 double crossover with two turnouts set for one divergent route. Ku, KL, XL, and XR all have convergent rails with opposing polarities.



10. Shinohara code 100 double crossover with two diverging routes set simultaneously. The convergent rails at Ku and KL have the same polarities, while those at XL and XR have opposite polarities.

Don't settle for all your locos sounding the same!

ESU now has **OVER 100** "LokSound" files to choose from!



Because "Close Enough" is no longer "Good Enough"

LokSound.com

“I can crawl most engines through the crossings without any shorting or pinching hesitations.”

While you can protect K-crossings by setting both divergent routes simultaneously, the X-crossings and point-to-stock rails have opposing polarities no matter what.

The point-to-stock rails do not typically cause problems, so let's look at some possible solutions for the X-crossings.

For the new-version Shinohara code 100 double crossovers, I recommend setting both divergent routes simultaneously to eliminate the K crossing shorts.

The new version has sufficiently insulated the X crossings to eliminate any shorts, whether operating DC or DCC.

If point-to-stock rail shorting should occur, I recommend gluing a 5- or 10-mm styrene strip to the outside of the open point rail on the divergent routes.

Removing the metal crossbars and wiring the point/stock rails together and adding single pole double throw (SPDT) power to gapped X-crossings would be a superior solution.

I have run a wide variety of equipment through the new-version double crossovers and have yet to experience X-crossing or a point-to-stock rail shorting problems.

I have also not experienced any pinching or wobbling as engines traverse the new-version code 100 double crossover. I can crawl most engines through the crossings without any shorting or pinching hesitations. Any hesitations have been due to dead spot stalls.

LIGHTING WITHOUT WIRING™

Fiber optic lighting for buildings and scenery

**10% Discount
on ALL
Lamplighter®
Units**



Get My
10% OFF!
Code

dwarvin.shop/MRH

DWARVIN

ADVERTISEMENT

RailPro™

**NEW
TECHNOLOGY**

**RE RING™
ENGINEERING**

DCC + RADIO CONTROL
HO Scale Locomotive Module

**ULTIMATE
SERIES
SOUNDS**

**TRUE
MOTION
TECHNOLOGY**

**LIGHT
EFFECT
EDITOR**

**DIRECT™
RADIO
+NET**

New Sound Technology and Mathematical Model Motion Control + more!!!



+



Equals
"DUAL MODE"
Control by DCC +
Radio Control

**Click Here to
Watch Video**

For more information visit our Internet site: www.RingEngineering.com

DOUBLE CROSSOVER WIRING | 13

A LIGHT GOES ON

Old-version Shinohara double crossovers with the twin metal crossbars on the point rails are another matter entirely, and the solutions are much more elusive.

Wheel backsides making contact with the vertical surfaces at the crossing apex typically cause the shorts, so my club tried to solve the problem by coating the vertical surfaces of the K- and X-crossings with nail polish.

Despite an occasional temporary success, our results proved to be unsatisfactory.

One of our members, Stephen Walsh, suggested we try using an 1156 automotive light bulb on the X-crossing as a short circuit limiting device in conjunction with the nail polish. Automotive light bulbs have been a trick for limiting short circuits since DCC was first put on the market.

Having both the nail polish and the light bulbs in place eliminated the X-crossing shorts completely. Only a combination of both proved successful.

I have found most of the shorts to be transient. They don't last long enough to make the bulbs glow or heat up enough to cause any concern.

However, it's probably a good idea to keep the bulbs readily visible just in case. A hard short would light them up, and a consist of three to five locomotives with sound will likely cause them to begin glowing.

“Having both the nail polish and the light bulbs in place eliminated the X-crossing shorts completely.”



REGISTER
(free)


[INDEX](#)

[TABLE OF CONTENTS](#)

ADVERTISEMENT

DR.DUINO™

FINALLY AN ARDUINO
COMPATIBLE MODEL
RAILROAD KIT!



CLICK HERE TO LEARN MORE!

DEMO CODE
INCLUDED TO CONTROL



SIGNALS



TURNOUTS



BLOCK
DETECTION



SERVOs



LIGHTING



MUSIC & SFX

ADVERTISEMENT

Make LocoNet wiring extremely simple!

ACCU-LITES, inc

Your DCC Center!


PM42
breakout
board



SE8C
breakout
board



BDL168
Multi-zone
breakout board



BDL168
Single-zone
breakout board



Now Offering SNAPS! in packs of 6 or 12 pieces! [CLICK TO LEARN MORE ...](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

DOUBLE CROSSOVER WIRING | 14


In short, you can dampen DCC shorting problems on Shinohara double crossovers with a little nail polish or liquid tape and an automotive taillight bulb.

The whole solution costs less than a dollar. There is no need to cut any gaps, remove any metal crossbars, isolate the double crossovers, or provide SPDT switching.

BREAKING IT DOWN

For our club solution, we wired two bulbs into the red lower (RL) and red upper (RU) feeder wires, between the circuit breaker and the tracks [11]. This would also work for the blue wires.

Alternatively, you could try a one bulb solution by wiring a bulb into either the red or blue bus wires between the DCC command station and the circuit breaker [11].



11. One and two-bulb solutions for Shinohara double crossover shorting. The yellow circles represent light bulbs.

ADVERTISEMENT

TamValleyDepot.com




Home of the
Frog Juicer

Dual
Frog Juicer

Automatic DCC Polarity
Reverser can be used to:

Power Two Frogs
Crossovers
Crossings
Automatic Reverser for
Turntables
Wyes, Loops
Circuit Breaker



Use with 2-10 Amp Systems

ADVERTISEMENT

www.SBS4DCC.com



SOUNDTRAXX®

NCE
The Power of DCC

Digitrax®

DCC Specialties
INNOVATION FOR DCC

MRC
Model Rectifier Corporation

ACCUTRACK II
SPEEDOMETER

SPROG DCC
the DCC Programmer and Control Family

Digital
plus
by Lenz

TAM VALLEY DEPOT
Great Electronics for Great Model Railroads

TEAM DIGITAL, LLC
Improving the world of DCC

N - HO - HOOn3 Scale Trains

ADVERTISEMENT



NEW DPM®/Roomettes Combos

- Save with 2-in-1 kit combos
- Includes DPM kit and Roomettes interiors
- With Just Plug® compatible LEDs

Click to purchase
WOODLAND
SCENICS®.com

REGISTER
(free)


[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)



12. Four-bulb shorting solution for Shinohara double crossovers. Note that you will need to cut four extra gaps into the track near the arrows to use this solution.

The gaps at G and H are not strictly necessary, but I like to have only one bulb in the short circuit path. Without those gaps, some of the short paths will have two bulbs in parallel, which increases the maximum allowable surge current, and there can be a hard short if the points are not set correctly.

The one- and two-bulb solutions will result in the bulbs affecting your entire layout (or section) which may not be what you want. A four-bulb solution as shown in [12] will affect only the double crossover.

If you choose to use a SPDT switch on the four-turnout frogs, you must place the switch machine feeder wires at the arrow points as shown.

The four-bulb solution does not isolate the double crossover, but you cannot have any track feeder wires between the bulbs and the crossover on the red rails or the circles and the crossover on the blue rails.

You must force the short currents to go through one bulb to complete the circuit.

If you utilize the four bulb solution do not do any gapping or soldering at the four ends of the double crossover tracks themselves.

Only four ties separate the point rail contact points from the end of the double crossover, and you do not want to damage them. Put your gaps and solder contacts at least an inch or two outside of the double crossover.

THE CIRCUIT BREAKER

For our DCC testing, we used a Digitrax PM42 circuit breaker set at a trip current of 1.5 amps and with a delay time set to approximately 500 milliseconds (the lowest-current trip point and the slowest circuit breaker delay time).

Since the bulbs do not light up, the current trip levels (which range from 1.5 to 12.0 amperes) should work in conjunction with the circuit breaker delay time of 500 milliseconds.

The PM42 is a mechanical relay type of circuit breaker. It is more sensitive to current surges than solid-state circuit breakers.

If we can make the bulb enhancement system work with a PM42, it should work with other circuit breakers, too, provided that we adjust the circuit breaker delay time to 500 milliseconds.

SOLUTION RATIONALE

A metal-to-metal short at the X-crossings would result in all current being diverted through the short, with no current delivered to the engine motor and no voltage drop across it.

If you wire a bulb in series with a metal-to-metal short, then all the voltage will be "on" the bulb, causing it to heat up, thus increasing the bulb's resistance and clamping the current. For an 1156 bulb, the DCC clamp current is about 3 to 3.1amps.

Coating the bare vertical surfaces of the X-crossings with a dielectric material transforms the metal-to-metal short to a metal-insulator-metal capacitor.

For the club's initial application, we used nail polish as the dielectric material. Since then, have learned that J. and B. Weld, though a little more difficult to apply well, produces stronger results and lasts much longer than nail polish or liquid tape.

If the insulator material is thick, the capacitance and capacitor charging currents are low. Shinohara's new-version double crossovers have thick dielectric material coating the horizontal surfaces of the X-crossings and the resultant capacitor charging currents go to essentially zero.

However, if the dielectric material is thin, the capacitance and capacitor charging currents will be greater. With thin-dielectric coatings, the charging currents under DCC voltages may be sufficient to trip the circuit breaker, even though the capacitive "short" and the engine motor draw current.

In fact, the locomotive draws enough current to keep most sound decoders going, even if the locomotive is moving at a crawl.

A bulb placed in the circuit reduces the capacitor charging current and avoids exceeding the breaker trip current, without affecting the current flow through the motor. As long as the capacitor charging times are short enough, the load receives its full input voltage.

While this article specifically dealt with Shinohara double crossovers, I would not be surprised if results would be similar for other crossings.

Our club had crossings that consistently shorted-out when traversed by any engine previously, so we solved the problem by removing the crossings!

This was before we stumbled across the bulb-enhanced double crossover solution. We still have the crossings, so maybe we need to put them back?



CONCLUSION AND ACKNOWLEDGMENTS

I hope you find this article useful. I suspect there to be a lot of Shinohara double crossovers still out there – they have been the only game in town if you want a factory-made double crossover. So have at it and let us know what happens.

I need to acknowledge the help of the Old Newburgh Model RR Club in Walden, NY which provided all the double crossovers used for testing. In particular, I'd like to thank members Steve Walsh, George Moore, Peter Bach, Tom Smith, and Ed Miller.

Steve first proposed the bulb enhancement idea, and George provided the test trackage. Tom provided the DCC function, with Ed and Peter doing a lot of the early engine testing. I am also grateful to Steve Daggott for his help and advice. ☑



**Use our custom
Google search on the
MRH website to find
topics of interest**

CLICK TO FIND OUT MORE



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

From first train set to railroad empire...

Our complete line of DCC products grows with you. Discover the fun!

- Designed and manufactured in the U.S.A.
- Preferred for ease of use and ergonomic design
- Unlimited scalability for any size model railroad
- Plug-and-play means more time running trains
- Great customer service and excellent support



Visit our new and improved web site for all your DCC needs!

- Get the latest new product announcements
- Watch our detailed how-to videos
- Browse the all-new Information Station
- Enjoy secure online sales, day or night!



See your dealer

Visit **ncedcc.com**



MRH MARKETPLACE




ITLA Scale Models Inc.

www.ITLASCALEMODELS.com

Modular Wall Systems

Fine Scale, "Configurable & Stackable"
Wall Kits in Laser Cut Wood



Laser Etched Wood Kits

CLICK HERE FOR MORE INFORMATION
www.itlascalmodels.com

**Make your model railroad
layout come alive.**



**NEW
MODERN
CREW
FIGURES**

<https://miniprints.ca>

Craftsman-quality custom figures
N, HO, S and O Scales

mini prints
it's the little things that matter the most

LOOK
at what's new at
Black Cat this month

Click here for
our website

CNR
Wood chip service
former SS box car
N & HO scale



Black Cat Publishing
(204)489-5005
ajfergus@mymts.net
blackcatdecals.com



Squeaky's Trains

Handcrafted & Exclusive Models
DCC Products, Service, Installations

Let's play with trains!

Offering:
SoundTraxx, TCS, NixTrainz,
Atlas, RailPro, MTO Battery, Kadec,
and many more Railroading Supplies!

SqueakysTrains.com



MRH MARKETPLACE | 2

Out with the old, in with a NEW generation!



Signal Animator/2
Block Animator/2
Grade Crossing Pro/2



New features, improved detection!

Please visit our website and online store!

LOGIC RAIL™
TECHNOLOGIES

(281) 251-5813

info@logicrailtech.com

www.logicrailtech.com



P.O. Box 6 Paonia, CO 81428

Ph. 970 527 4586

Made in The USA

Cast resin items for All Scales.

Tunnel portals, bridge piers, abutments,
culverts, and retaining walls.

Trackside details and sage brush tree
armatures.

"FREE SHIPPING see website for details"

Model Railroad Control Systems

Geoff Bunza Project Boards

DCC Occupancy Detectors

CMRnet Compatible Nodes

Layout Telephone Systems

RFID Switchlist Generator

Switch Machines and Drivers



Click Here

WE'RE BEHIND YOU ALL THE WAY

SceniKing®.com

...nothing compares...

Click to learn why!

Great Decals!™

FEC, Interstate, Virginian

Railway, & L&N Titles

After Hours Graphics Line

Coupler Gages and More

In O, S, HO, and N Scales

**Get me
some!**

**Our kits look great
from behind too!**



Kit HO-3011

www.interactionhobbies.com

MONASHEE

LASER

ENGINEERING

MANUFACTURERS OF FINE RAILROAD
STRUCTURES AND ROLLING STOCK MODEL KITS

**COME VISIT US
CLICK HERE**

PRECISION DESIGN CO.

CUSTOM DECALS FROM
YOUR OWN ART IN JUST ONE DAY

PDC.CA

FULL COLOR & SOLID WHITE

Human[c]ity Junction

Model Railroad Videos | Tutorials, Reviews, Interviews, Hangouts

YouTube Channel Sponsored By

CMR Products | 7% off on House Brands

Iron Planet Hobbies | 10% off and Free

Shipping in the USA

Use Discount Code "HUMAN"

Please visit us out at www.humancityjunction.com



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

MOUNTAIN SUBDIVISION HOBBIES

www.modelrrsupply.com

FREE USA SHIPPING OVER \$49.00

MRH Readers save with code:

MRHMAG19

click me!



**Pursuing
Excellence**

THE TRAINMASTER, LLC

Detailed Craftsman Kits

www.TheTrainMaster.com




WESTERFIELD
GOLDEN AGE LINE
MODELS, LLC

NEW KIT: AT&SF
Fe-Q/Fe-R/Fe-V



westerfieldmodels.com

click to learn more!



East Coast Circuits
Innovating Your Model Railroad Layout

P.O. Box 25412
Providence, RI 02905

Lighting Circuits For Your Layout

Random Lightling Circuit - Burning Fire Circuit
Traffic Light Circuit - Crossing Signal Circuit

Custom Lighted Vehicles
HO & O Scale Emergency Vehicles
HO & O Scale Trucks & Cars

Eastcoastcircuits.com

Eastcoastcircuits@gmail.com

STRUCTURE KITS!



HO AND N SCALE

www.monroemodels.us

**Your ad here could
reach 65,000+
for as low as \$112
a month.**

Click to learn more ...

Floquil/PollyScale stash running out?



MRH has mapped the old familiar colors
to readily-available acrylic paints.

[illegible]

**MRH Registered Readers: Download your
FREE Post-Floquil acrylic painting eBook**

Want a hardcopy version?
Post-Floquil acrylic painting guide: \$16.99 (MRH Store)



REGISTER
(free)

INDEX

TABLE OF CONTENTS

MRHMAG.COM

INDEX

TABLE OF CONTENTS

Easy to build town and city structures in N and HO scales



**V.S. ROSEMAN SHOWS THE MANY
POSSIBILITIES OF JUST ONE HIGH-RISE HOTEL KIT...**

EASY TOWN AND CITY STRUCTURES | 2

1. N scale CMR Park Hotel kit, assembled in a downtown city setting.

Model Railroad Hobbyist | May 2021



A FRIEND OF MINE RUNS A HOBBY SHOP. Recently, a customer asked to have the N scale CMR Park Hotel kit assembled for his layout, and my friend hired me for the job. The Park Hotel kit, available in both HO and N scales, builds into an impressive and realistic tower hotel [1, 2].

CMR structure kits are laser-cut acrylic that is rigid and dimensionally stable. Most solvent cements work on it. Despite the Park Hotel's size, it assembled easily.

I built and painted the kit in sections, and set each aside to dry overnight. In the morning, I had an epiphany. The building has five distinct sections and a roof, each of which I could use as an individual building [3].

Before completing the kit, I decided to test some of these smaller structures in an N scale layout setting. I added a few removable decorations and photographed them. Depending on how you choose to use the parts, you can make several structures from just one kit.

The eight-story portion of the model above ground level could make a good-sized hotel or apartment building by itself. It takes up very little space on a layout.

I made up some signs on my computer to name it the "Hotel Rexford Tower" and built a support framework of plastic strips – Plastruct or Evergreen works for this. There are a number of



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)



illuminated and animated signs available in hobby shops that could make the hotel a real showpiece. I added some fine black sandpaper to simulate a flat roof.

To dress-up the first floor, I drew up red awnings on the computer and printed them on cardstock. I could have used painted styrene, but I wanted to use some of the fancy emblems some hotels have.



2. (Left) N scale CMR hotel in a resort setting by the sea.

3. (Above) Hotel model shown in five segments.



4. I made a smaller city hotel with awnings for upscale shops on the first floor. I drew designs and printed these on cardstock.



5. A view of the Rexford Tower back wall. I added a large title sign and ad for the hotel coffee shop. The little parking lot and signs add more interest than butting the hotel against other buildings. A park or lawn with some trees would be another interesting detail.





6. Front view of Rexford Tower.



7. Rexford Tower set into an N scale city module.



I thought the windows looked bare, so I simulated tied-back curtains from squares of colored paper. I cut a V-notch in the bottom edge of each curtain. A hotel would probably have all the same color curtains, but you could simulate an apartment house with curtains and shades of different colors in each apartment.

As this building section has no entrances, I photographed some interesting doors in my neighborhood and printed them. I calculated the doors to be 7' tall, which is almost exactly $1\frac{1}{2}$ " in 1:160 scale. 8' doors would be close to $5\frac{1}{8}$ " tall.

I ran a black marker around the edges to eliminate the white paper rim. I sealed both front and back with Dullcote to help resist moisture that might warp the paper. I framed the doorway with 0.030" styrene from Plastruct or Evergreen to add depth.



8. City of Landia Municipal building with decorations in layout setting.

You can make the back of the model (the side with very few windows) more interesting if it faces a park, one-story building or a small parking lot. In this case, I added billboards to advertise some of the hotel's features to the blank wall areas [5]. You can advertise any product or service you like, of course.

The three-story section of the kit looked like it would make a good municipal building. This important structure can include town, county, or city offices such as the water department, police station, or other essential services. This structure could be an office building such as the railroad's division offices, or could hold offices of individual firms [8].

Before TV and radio, public entertainment included concerts, traveling theatrical plays, and vaudeville shows. By 1910-1920, movies became a huge part of the entertainment industry. The ground floor of the kit would make an excellent theater.

Some small local movie theaters still survive, but most have been repurposed as meeting halls, or for other uses. You could place posters (available in hobby shops) for movies or Broadway shows visiting town on the walls or on easels in front of the theater. I built an old-fashioned marquee for this model, but you can replace it with a more modern illuminated marquee [9-11].

You could place some of the kit's upper floors above the theater building to serve as offices. There are many examples where this was done, a few of which are famous. Chicago's Lyric Opera House has offices above it, and the Masonic meeting hall in Glendale, California has a movie theater on the first floor.

A post office was often placed next to the railroad track, with loading doors on the side or back. Sometimes train loading would be done from one or more spur tracks off the mainline [9-13].

Alternatively, this building could be a city hall or municipal building, depending on what your town needs. I didn't use the



9. Park Hotel kit's main floor portion decorated as a town auditorium, theater or meeting hall.



10. Main floor of kit with homemade movie marquee.



11. Shore movie theater with signs photographed at Coney Island.



12. Set-back style structure shown as a large post office in a street view.



kit's elaborate hotel roof as seemed too big for any of the smaller structures, but you might want to try it.

The third or fourth section could be an apartment block, condo, small hotel, clinic, or office building [14, 15]. The stripes I have on the model are often a different color stone or brick, and can be any color, but usually are neutral brick or gray, tan, or brown stone.

For each of these smaller buildings, you'll need to add an entryway. You can make a simple entrance by photographing a real entry, then sizing, printing, and gluing the photo to your building. For added flair, I like to add a styrene frame to it [16].

Adding vestibules with doorways provides many more possibilities. For vestibules, I printed the door on thin coated inkjet paper and folded it around a small block of basswood [17].




13. Post Office with railroad loading platform wrapping around the front of the building and along the side.



14. Apartment house with tan and gray stone. This could also be a condo, small hotel, or small office block.




15. Tannenbaum Arms can represent an apartment complex or hotel that has been modernized with an aluminum entry vestibule. I painted strip styrene blue, and cut it to match the window height for shutters on first floor. The rooftop air conditioning unit is scrap styrene, although there are commercial kits available for ventilators, air conditioners, and other typical fittings.



windows' height, paint your desired color, and cut into individual shutters (3).

16. To make a simple entryway, find a photo of an entryway, scale to size, and print on cardstock (1). Frame with styrene strips and secure with contact cement (2). To dress up your building's windows with shutters, cut a strip of 0.15"-thick styrene the same width as your



17. To build a vestibule entry, photograph a door and print on cardstock (1). Score the cardboard along the gray lines (2). Fold the sides (3) and top (4) as shown.



Large roll-up doors could lead to a basement parking lot or can represent loading doors. For a panel type roll-up door, I folded cardstock around a block of basswood and added a styrene roof [18, 19].



18. roll-up garage doors or loading doors fitted into a vestibule.



19. This roll-up door is a flat print. I did not add a frame for the shadows made the door look three dimensional.

I wanted a modern glass-and-aluminum vestibule for the Tanenbaum Arms to represent that the building had undergone modernization [20]. I covered a photo of a doorway in my neighborhood with a 1/8"-thick piece of acrylic. I cut door frame from dull silver wrapping paper to represent aluminum, laid it on top, and glued it all together by carefully applying contact cement around the edges with a toothpick [21].

If these structures represent fireproof construction, fire escapes are not necessary. However, it is possible that they are "semi-fireproof," in which case you'll want to add fire escapes. Fortunately, Tichy has a nice N scale installation in his line of plastic kits, and several other manufacturers have good N scale fire escapes, too.

When I figured how the CMR Park Hotel kit could be divided up into so many different kinds of city buildings, I called a friend with



20. Aluminum vestibule for the lobby of Tanenbaum Arms. Older buildings that have been modernized often feature this type of entry.

an N scale layout so I could take the photos you see here. Together, we agreed that the conversion would be an easy project that would yield structures that might encourage modelers to really "think outside the box." ✓

★★★★★
RATE THIS ARTICLE



21. To make modern aluminum vestibules, begin with a photo of a lobby or entry scaled to size and printed (1). Overlay it with a 1/8"-thick piece of clear acrylic, cut to size (2). Cut a frame from silver wrapping paper, and position it on the acrylic (3). Use a toothpick to apply DAP Weldwood or similar adhesive around the edges.

V.S. ROSEMAN




Victor got his first train, a Lionel, at age 3. Victor graduated from the Pratt Institute with BFA and MS degrees and taught fine arts in high and junior high school for 30 years and is now retired.

Victor has written many articles and several railroad related books over the past 35 years. He's also done many freelance projects for Walthers, Atlas and other model manufacturers. ■



RATE THIS ARTICLE

Did you see this article?



Scratchbuilding stone structures in O, HO, OO, N

Get the May eBook now

← *click here*


In **MRH** **RUNNING** **EXTRA**

Your ad here could reach 65,000+ for as low as \$222 a month.

Click to learn more ...

ADVERTISEMENT

HARVEST SOME **REALISTIC GRAIN BINS**



- ☒ Realistic galvanized steel appearance
- ☒ Easy assembly
- ☒ Prototypical corrugations
- ☒ Variety of stock sizes
(Custom sizes available on request)

Grain Belt Models™

Click anywhere on this ad to learn more...

ADVERTISEMENT



Introducing **T-H-E LUMBER STORE**



ROTATING STORAGE RACK

On its own, or fully loaded with Mt. Albert Scale Lumber!

handlaidtrack.com

1-888-252-3895

Seen these TMTV videos?



Bringing it all together:
signaling demo



Modeling work car
undersides



Run like a Dream: first
flawless running ingredient

Watch now ...

7 day rental: 1.99 | buy: 2.99

Or become a member and get unlimited access (500+ videos)




www.trainmasters.tv

Registered MRH reader?

SAVE 10%
click here

BUILDING A SMALL N SCALE LAYOUT PART 2



Model Railroad Hobbyist | May 2021

DAVE KILBORN DEMONSTRATES HIS SCENERY TECHNIQUES...



THIS MONTH I CONTINUE THE CONSTRUCTION OF MY SMALL N scale layout, moving on to scenery. I want this small layout to be light enough that I can easily move it myself, so foam will be the main component of the scenery base.

I want to have a mountain with tunnels on one side that extends to the middle, acting as a view block from one side to the other. I would have a segment of another mountain on the other side of the river with a tunnel there [1].

In the flat area at the end of the “peninsula” of the mountain, I want to put a small town scene set roughly in the late 1970s.

BUILDING A SMALL N SCALE LAYOUT | 2

The town will include:

- some sort of small industry at the spur
- a restaurant
- a gas station
- a small-town hotel
- a passenger depot at the passing siding


I plan to add an old, abandoned mine off the spur on the other side of the mountain. With these rough ideas in mind, let's dive into building the mountain with foam.

BUILDING A SMALL N SCALE LAYOUT | 3

FORMING MOUNTAINS WITH FOAM

There are different methods of making mountains out of foam, and one of the best tutorials I have seen comes from *MRH* blogger Rick Reimer (On30guy on the *MRH* forums, rupheandtumbelle on YouTube). His video gave me a great starting point: www.youtube.com/watch?v=MQ_PF27nA4s.

I cut a few pieces of foam to go into the two corners of the longest tunnels on the left side of the layout diagram. These pieces will act as a base to build up the "cover" over the tunnels as well as tunnel liners [2].



1. The black lines represent the contours of the mountains I wanted to build. I wanted the mountains to dwarf the trains and serve as a view block to divide the layout into separate scenes.



BUILDING A SMALL N SCALE LAYOUT | 4

I also added a divider between the two tracks so that you can see tunnel walls through the portals if you look from the right angle. I cut a couple more pieces to form the inside of the tunnel and the base of the “peninsula” and glued them into place.

PREPARING THE TUNNEL FLOOR

Before proceeding further with building the mountain, I took advantage of the easy access to scenic the inside of the tunnel. First, I covered up the track with tape to protect my weathering job.



BUILDING A SMALL N SCALE LAYOUT | 5

I mixed up a batch of my own ground goop using vermiculite, CelluClay, craft paint (any earth/rock tone) and water. I didn't use any specific recipe for the mix, but after adding the dry ingredients, I added water little-by-little, mixing with my fingers until it was the consistency of thick oatmeal.

I applied the goop using my fingers, attempting to keep it as thin as possible because of its long drying time. I wanted to cover the foam and fill any undesired cracks or crevices. I let the goop dry overnight [3].

2. I formed the tunnel entrances on either side of the mountain, building up the height of the corners to support the top of the tunnels in each corner. I used weights to hold the foam down as the adhesive dried.

Did you see this article?



Scratchbuilding
stone structures in
O, HO, OO, N

In **MRH** **RUNNING**
EXTRA

Get the May eBook now

[click here](#)



REGISTER
(free)


[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)



3. I scenicked the inside the tunnels before putting on the top.

CREATING THE TUNNEL WALLS

My next step was to make the tunnel liners. This was my first attempt at carving rocks from foam, so I began with the less-conspicuous tunnel liners. I used a couple of old kitchen knives to randomly cut, slash, and gouge the foam to look like blasted rock [4].

I noticed that the seams between the chunks of foam were too uniform to be realistic. This wasn't a big deal in the tunnel, but I would have to address it on the mountains.

Using my wire brush, I knocked off any loose pieces of foam and worked to blend the "rocks" together. I vacuumed up the loose material before grabbing my palette with burnt umber, burnt sienna, and yellow craft paints. I kept a dish of water handy to create washes.



4. I used kitchen knives to rough-up the foam to look like tunnel walls.

I mixed burnt umber with a bit of water and put a base coat on the foam. I added blotches of yellow wash and burnt sienna wash, and blended them for color variation. Washes of white and black added even more variation. I finished with a thin black wash over the whole tunnel wall and floor to fill cracks and tie everything together [5].

FINISHING THE TUNNEL

I added some fine real dirt material to add some color and texture, followed by various colors of fine talus or ballast from Woodland Scenics to finish off the inside of the tunnel [6]. I secured it all with Scenic Cement.

An application of Kato ballast along the profile of the Unitrack from inside the tunnel to several inches outside the tunnel finished it off [7]. Kato ballast matched the Unitrack nicely and looked like the type of ballast I wanted. I applied alcohol with


an eyedropper to wet the ballast and added scenic cement to secure the ballast.

BUILDING THE UPPER TUNNEL


I found pieces of foam to cover over the lower tunnel and act as a liner for the upper tunnel. I trimmed each to fit and I added a piece to the center section on the inside of the two upper tunnel openings [8]. I followed the same steps to complete the inside of the two upper tunnel openings as I did the lower two.

BUILDING UP THE MAIN MOUNTAIN

With the insides of the tunnels complete, I built up the rest of the main mountain area with the remaining foam. I sought to use the pieces as effectively as possible to limit cutting and waste [9]. I worked for a natural slope as I built the mountain up.



5. A thick wash of burnt umber, followed by blotches of yellow, burnt sienna, white and black washes gave the tunnel some color variation.



6. I put the tunnel portal in place to get a feel for what it would look like from the normal viewing angle. The tunnel wall turned out darker than I would have liked, but it looked good enough from this angle.



7. I added natural dirt and Woodland Scenics fine ballast to the floor of the tunnel. I used Kato Unitrack ballast for the tunnel entrance.




I wanted the mountain to be large enough to dwarf the trains, yet still be small enough that moving it by myself would be manageable. I kept adding layers until it looked about right, about 10" at the highest point above the lowest track elevation. The total height of the foam, including legs, was approximately 13".


I needed to ensure there was adequate access to the inside of the tunnels for maintenance – track cleaning or clearing a derailment. I conducted some tests to determine how much space I needed, and the result was a 6" opening on the side to allow a bit more than 4" of clearance on the inside track [10]. The void in the tunnel also allowed me to use less foam.

BUILDING THE SMALL MOUNTAIN


With the main foam mountain built, I turned my attention to the small mountain section across the river on the opposite



8. I trimmed and fit pieces of foam over the lower tunnel openings. I matched the inner height to the outer with more foam. In the upper-center, I had just begun finishing the inside of the upper tunnel.



9. Here, the foam structure of the mountain was nearly complete, with only small pieces needed to add depth.




10. As part of the mountain construction, I built a large area for easy access to maintain the tunnel trackage. I may cover this area with a piece of styrene or foam-core for display purposes.

end of the layout. I followed the same method I did with the main mountain.


With a bunch of off-cuts and pieces of foam, I formed this second peak almost like using wooden blocks. I stacked and fit the pieces until the shape looked right, and I had the tunnel formed.

I began carving the foam to simulate rock formations and make the mountain look less blocky and more natural. I had difficulty picturing the final result, and was concerned it would look off, but I kept going anyway. If it didn't look right, I could always redo it.

As I reviewed my work, the obvious horizontal lines of the foam layers looked too uniform [11]. I had some lightweight spackle, so I tried using it to fill some of the horizontal lines and add additional texture. When it dried, I used a wire brush to rough-up the texture [12].



11. I built up the smaller mountain and started carving the foam. You can see some of the tunnel liner paint accenting the horizontal lines in the foam.



12. Lightweight spackle added texture and helped fill horizontal lines in the foam.

I test-fitted the tunnel portals, and decided I should add something around them to fill the gaps. I cut pieces of plaster cloth to fit in around the tunnel portals, wet them, and pressed them into place on the foam. With the plaster still wet, I pressed the portals into the opening to hold the cloth in place and eliminate any remaining gaps [13].

FINISHING THE SMALL MOUNTAIN

I mixed more washes, and painted the rock surface. I used a base coat of gray craft paint with a bit of black and brown mixed in. I added water to the paint so it flowed better over the rocks and into the nooks and crannies. With the base coat still wet, I blotted-in the different washes and blended them in to add color variation to the rocks [14].

Once I was satisfied that I had a nice variety of colors and intensities in the rocks, I left it to dry overnight. The next day, I



13. I used plaster cloth to fill the gaps around the tunnel portal. After putting the pieces in place, I pressed the portal into the opening and ensure it was snug, and no gaps remained.



14. I mixed a base coat of gray craft paint with a bit of black and brown, and applied it to the small mountain. I blended various color washes into the base coat.

mixed a dark wash and covered the rock face, working it into the cracks and crevices to bring out the shadows and detail [15].

I wasn't satisfied with the result when it dried. The rocks were generally too dark. I lightened them up with a wash of Woodland Scenics Stone Gray liquid pigment.

I followed this by dry-brushing a mix of white and gray onto the edges of the rocks to highlight them more [16]. I used white and gray on the same palette to allow easy variation. If I applied too much highlight, I could easily blend it with water, but sometimes what I thought was excess paint actually looked more convincing.

CARVING THE MAIN MOUNTAIN

Turning my attention to the larger mountain, I used my knife to hack away at the foam, taking larger chunks out to form a more



15. A dark wash over the surface brought out the shadows and details of the rock.



natural slope, some plateaus and rock faces. I also wanted to form a cut to the right of the tunnels for a “hiking” trail for my 1:160 folks.

As I completed hacking and slashing the foam, those horizontal foam lines glared at me again. I didn’t have enough lightweight spackle to complete the large mountain, so I tried Foam Putty from Woodland Scenics instead.

I found the foam putty easier to work with than the spackle. I could build up layers of the foam putty more easily, which allowed me to create other formations. It was also easier to carve.

This mountain was much larger than the smaller one, so I decided to enhance the variety with a few Hydrocal rocks. I hot-glued the rocks to the foam, and filled-in around the edges with foam putty to blend them into the mountain [17].



16. A light wash of Stone-Gray Woodland Scenics liquid pigments lightened the rocks. Gray and white dry-brushing highlighted edges and brought out even more texture.



17. I shaped the foam on the main mountain and used foam putty to fill some of the horizontal seams. A few Hydrocal rock castings added variety.

I test fit the tunnel portals to make sure my passenger cars will go through them without touching the portals as they are on a curve. Once verified, I hot glue the tunnel portals in place.

I filled-in around the gaps with the foam putty. Some gaps were larger than I wanted, so it took some time to build up the layers of foam putty to blend the portals into the mountainside [18].

COLORING THE MAIN MOUNTAIN

I applied the same base coat to the large mountain as I did to the small one, using the same technique. I blended-in several colors of wash while the base coat was still wet [18]. When that dried, I added the dark wash to enhance shadows and texture



18. After attaching the tunnel portals and Hydrocal rocks with hot-glue, I filled the gaps with foam putty to blend them into the mountainside. Then I put on the base coat and blended the various color washes.



19. When the base coat and washes dried, I applied dark wash to highlight the shadows in cracks and crevices. I dry-brushed white and gray highlights onto the edges of the rocks to finish.

in the rocks, followed by brushed-on white and gray highlights on the rock edges [19].

Overall, this process was a lot of fun. There are areas where I didn't like the results, but the foam is easy to change and repaint. For many years, I was afraid to try scenery because I knew I would inevitably make mistakes, and it wouldn't look right, but now I have confidence to know I will find solutions when I do.

While I am not always 100% satisfied with my results, I have learned to say, "good enough" and move on. I can always come back and change things later on. Next time, we'll get into adding ground cover and foliage. ✓

★★★★★
RATE THIS ARTICLE

DAVID KILBORN



David lives in Saskatoon, SK Canada with his wife, his mother and his two adult children. He has loved model railroading since four years old, when he saw his dad's model trains.

Issues with dexterity and vision in 2013 resulted in a switch from N scale to HO scale, but he missed N scale. When the Covid-19 lockdown hit, he decided to build this N scale layout that he wanted since he was 16.

David has worked at a remote mine site for 18 years, supporting management systems and regulatory compliance. He loves to travel, and looks for opportunities to do so by train. He plays bass guitar and dabbles in writing music and arranging. ■

Did you know?



MRH Media
includes ...



**Model Railroad
Hobbyist magazine™**

Free eZine
Browse back issues ...
Must register (it's free)

[click here](#)

**MRH RUNNING
EXTRA**
Apprentice with savvy modelers

Paid eZine
Browse back issues ...
Must buy to read

[click here](#)

**Model Railroad
Hobbyist Store**

- DVD videos
- Downloadable videos
- Paperback books
- Downloadable eBooks

Browse the store ...

[click here](#)



TRAINMASTERS.TV

Watch videos
Membership video site
Hundreds of videos!

[click here](#)



LOOK column

Model Railroad Hobbyist | May 2021




JEFF PALMER GIVES A FIRST IMPRESSION OF MODEL RAILROADER'S NEW 10-YEAR ARCHIVE: 2010-2019 DVD SET

I'VE READ MODEL RAILROADER MAGAZINE (MR) SINCE I WAS GROWING up in the 1960s, including many articles on how to build structures, cars, and locomotives. When I was working to obtain my Master Model Railroader (MMR) certificate from the National Model Railroad Association (NMRA), I found articles from Jack Work to be especially useful.

Jack wrote the best articles about bridges, in which he highlighted the details of his good construction techniques. I read his articles over and over, searching for the fine points of construction, detailing, and "how to" techniques. I didn't remember Jack from my teenage years in the 1960s, but when *MR* came out with its 75-year archive in 2009, I jumped on it.

While the internet is good, this archive was better, with three DVDs of material, including every issue published from 1934-



1. The cover for *Model Railroader's* 75-year collection.

That was 10 years ago. A few months ago, *MR* announced the 10-year archive for the magazine [4]. I assumed that this archive would be an extension to the original 75-year archive and that it would process (install, store, and search) similarly. I had hoped to merge the two archives and use them as one library. If they were separate, that would be OK too.


With my past experience with the *MR* 75-year archive, I was looking forward to this addition. As before, it arrived in the mail. Moments later, I had it unpackaged, and loaded the first DVD into my drive.

The DVD did not start as expected. I was expecting it to launch a program to provide me with a menu or simply to start querying

2009 [1]. When it arrived in the mail, I installed it on my computer and began perusing history.

I typed “Mine” into the search and found the old articles by Allen J. Brewster from the 1970s that I used to scratchbuild an N scale model of a gold mine [2, 3]. I still have that model in my closet. It won my first model contest at my local hobby shop.

I use the 75-year collection over and over. It’s one of my most important research tools. I have used it for topics on scenery, rail care, detailing, locomotive reviews, and a host of other queries.



2. I found the search process on the original 75-year collection to be simple, and it searched the *entire 75-year library* of magazines.

me about installation options, but it didn’t. It did nothing, which alarmed me a little.

I double-clicked on Windows File Explorer to browse the DVD and see what was on it. There was no AUTORUN file to launch a program or play the DVD like a movie. Instead, I found two PDF files on the disc:

1. How to use
2. Model Railroader Disc 1

I was puzzled that there were no .msi or .exe files. I thought I must have missed something, so I clicked on the first PDF,


entitled “How To Use.” It was a one-page document explaining how to use Acrobat Reader [5].

That was disappointing. I read the document, to see if PDF documents had acquired new features or if there was a hidden script to execute to launch the archive. The DVD simply contained two PDF files.

Sadly, the PDF document didn’t reference the red link in the upper right-hand corner of the document – Main Menu – which initiates the second PDF file on the disc, “*Model Railroader* Disc 1” or “2,” depending on which DVD you have in the drive. Going to the Main Menu, the first six years of the archive came up, 2010-2015 [6].




3. I found Allen J. Brewster’s article about building a gold mine.



4. The cover for *Model Railroader*’s 10-Year Archive, comprising 2010-2019.


5. There were two PDF files on the DVD. The first contained instructions for using PDF files.



I was curious about the search capabilities of this archive, so I clicked on “Edit” and selected “Find” from the drop-down menu. This opened a search window and I entered “Jeff Wilson,” a popular author for *MR* who had written articles within the time frame. The search claimed, “No Matches found.”

I know Jeff Wilson wrote articles in 2010, so I clicked “2010,” which brought up all 12 issues for that year, January-December [7]. My search for “Jeff Wilson” yielded the same results.

I knew Jeff Wilson had an article in the January 2010 issue, so I tried one more time. I clicked on the January 2010 icon, which brought up the issue, and repeated the search [8].



6. The main menu for the first DVD shows *Model Railroader* covers from 2010-2015.



7. Clicking on a year brought up all 12 issues for that year.



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)


[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

This time, the search took me to the table of contents reference for him and to his article, "Model the Meatpacking Industry," on p. 48. Success [9].


This means that although you have access to all of the articles from 2010-2019, you cannot do general searches for information



8. Clicking on an issue icon brought up the specific issue.

on a specific topic on the DVD or year level. You have to search magazine by magazine.


Not wanting to miss anything in the archive, I ejected the first DVD and replaced it with the second DVD. This time I just clicked on "Model Railroader Disc 2." The second disc contains the last



9. The search function works only within a specific issue.

four years of the magazine (2016-2019), and a collection called “Special Issues” [10].

I clicked on “Special Issues,” and found 11 special issues that cover subjects like scenery, track plans, and lots of how-tos [11].



10. The second DVD contains issues from 2016-2019, as well as the Special Issues published from 2010-2019.

These special issues provide an abundance of ideas and inspiration. Having bought most of these special issues individually, I like having them in electronic form, and this is the best part of the archive for me.



11. Every special edition of *MR* published between 2009 and 2019.



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)

FIRST LOOK | 12

MR produced an excellent, searchable archive for their 75-Year Collection, but this 10-year collection fails to meet that standard. MR simply loaded electronic versions of all issues from 2009-2019 onto a couple of DVDs and called it a day.

I found the 10-year archive to be a disappointment. It certainly has the potential of saving shelf space, but purchasing the DVDs doesn't provide anything that subscribing to the electronic version of the magazine would not. ☑

★★★★★
RATE THIS ARTICLE

Did you see this article?



Safer airbrush cleaning solvents

Get the May eBook now

← click here

In **MRH** **RUNNING**
EXTRA

WEATHER

like a pro. (No airbrush required!)

Go from this ...



To this ...



Volume 1:
Freight cars

Volume 2:
Diesel locomotives

Click me to
LEARN MORE ...

“Simple, effective, and a lot quicker than an airbrush ...” - *Koos F.*

DVD or Digital download - From the MRH Store: store.mrhmag.com

Start the layout of your dreams now! No space? No problem!

Building a modular home layout with



TOMA

THE ONE MODULE APPROACH

Episodes in this video:

- 01.TOMA series introduction
- 02.TOMA design
- 03.TOMA benchwork
- 04.TOMA trackwork
- 05.TOMA wiring
- 06.TOMA structures
- 07.TOMA scenery, part 1
- 08.TOMA scenery, part 2
- 09.TOMA adding details
- 10.TOMA operation
- Bonus: TOMA make grass tufts

DVD
(4 disks)
\$29.99
~~\$44.99~~

Download
Avail. Now!
\$19.99
~~\$29.99~~ 11 files

DVD
4 disks

ON SPECIAL!

How to build toward
that eventual dream
pike now in the
space you do have.



Get the video!



SAVVY MODELER *Online*



RATE THIS ARTICLE

Model Railroad Hobbyist | May 2021



DCC speed matching made faster

YouTube model railroader **raillfan220** shows how to speed match three locomotives just using three CVs. He gives a superb explanation of the process using a whiteboard, making it very clear what he's doing to accomplish this task. Then he goes over to the layout and makes it happen!

So check out this video if you'd like to master DCC speed matching! ☒



▶ GREAT MODELER VIDEOS ON THE WORLD WIDE WEB



It's all about trains



*All things train related,
whenever, wherever.*

TRY
24TRAINS.TV
2 WEEKS
FOR FREE



WWW.24TRAINS.TV

On 24TRAINS.TV you can find:

videos | travel reports | magazines | vlogs
model railways | workshops | documentaires | holidays



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

MAY NEWS

column



Model Railroad Hobbyist | May 2021

RICHARD BALE AND JEFF SHULTZ
REPORT THE LATEST HOBBY
INDUSTRY NEWS ...



VIEW READER
COMMENTS

INDUSTRY NEWS

Atlas Acquires River Point N Scale Tooling

Atlas has completed the purchase of tooling for selected N scale vehicles from **River Point Station Scale Models** of Warwick, RI. The acquisition includes tooling for a 1992 Ford F-250 crew cab pickup, a 1992 Ford F-350 service truck, and various accessories. The purchase follows a 2020 announcement by River Point Station that the company intended to focus on 1:87 scale vehicles. For additional information visit shop.atlasrr.com.

NEW CLUB CARS



The **Chicago & North Western Historical Society** is selling HO scale kits for ex-Rock Island 40' boxcars patched for C&NW. Three cars are available with different numbers and slightly different patches. The models

THE LATEST MODEL RAILROAD PRODUCTS, NEWS & EVENTS

MRHMAG.COM

[INDEX](#)

[TABLE OF CONTENTS](#)

MAY NEW PRODUCTS MULTIPLE SCALES | 2

were custom produced for CNWHS by Accurail. For additional information visit www.cnwhs.org.




The **Soo Line Historical & Technical Society** is selling an N scale model of a 40' Soo boxcar. The model is based on a prototype built

at Soo's North Fond du Lac shops in 1951 and represents the first car in the home-built series painted without black ends. The model displays bold 4' lettering, and "Built in Fond du Lac" and "Nailable Steel Floor" slogans. The custom model was produced by Micro-Trains. For more information visit www.sooline.org.

NEW PRODUCTS FOR MULTIPLE SCALES



Adirondack Car & Foundry is booking reservations for HO and S scale models of a Newfoundland Railway NF210 diesel switcher. The models are based on the 3' 6" narrow gauge prototypes built by GMD in the 1950s.




The locomotives represent the first of a selection of NFLD rolling stock that will initially include an outside braced boxcar and a steel van. For additional information including placing a reservation visit adirondackcarfoundry.square.site.

MAY NEW PRODUCTS MULTIPLE SCALES | 3




Atlas has released an on-line catalog for Spring 2021 that covers all Atlas N, HO, and O scale rolling stock and accessories, including track products. The full-color catalog can be viewed and downloaded at download.atlasrr.com/Spring2021ArrivalsCatalog.pdf?mc_cid=6cc3158e7a&mc_eid=6bff0ec9ce.



Monster Modelworks has laser-etched basswood sheets that replicate Old Brick (left) and Aged American Brick. The material is sized for N scale and is available in 1/32" and 1/8" thick basswood. Etched corners for use with 1/8" thick

side sheets are available in N, HO, S, and O scale in both Old Brick and Aged American Brick patterns. For additional information visit www.larkspurlaserart.com.



New publications from **Morning Sun Books** include the *Trackside Around the Garden State 1950-1975*. Edited by John Canfield, this hardcover book features the photography of Bob Goin and John Dziobko, Jr. as they

document the EL, CNJ, and PRR in the northern portion of New Jersey prior to the arrival of Conrail.

Morning Sun has released the final volume of *New Haven Power* which features switchers and electric motive power from the smallest GE 44-tonners to the Alcos, Limas, and the EMD SW1200s. Electric coverage includes early electrics, "Virginians", "Jets", and post-New Haven electric operations by Penn Central. For additional information contact a dealer or visit www.morningsunbooks.com.



SoundTraxx is now selling the Mini Cube 3 speaker and baffle kit. The smallest speaker in the SoundTraxx line, it measures 12 x 3.3 x 3mm and is a half-watt 8 Ohm sugar cube type speaker. For more information visit soundtraxx.com/accessories/speakers/oval-speakers/mini-cube-3-oval-speaker-baffle.



Woodland Scenics is releasing a new Built & Ready building in N, HO, and O scales named Records & Recruiting. Measuring 4 19/32" x 3 5/8" x 4 1/2", it features printed interiors of a record shop, an Army recruiting station, and upstairs apartments. For more information visit woodlandscenics.com.

HO SCALE PRODUCT NEWS




New HO scale car kits released by **Accurail** include this Burlington Northern triple-bay covered hopper car. The model is based on a prototype built in January 1980.




The prototype of this Chicago & North Western twin-bay covered hopper car was built by American Car & Foundry.



Accurail has released kits for 36' double-sheathed wood boxcars in two Northeastern road names. The Boston & Albany version represents a prototype built in 1913. The Delaware and Hudson car displays a herald with the slogan "The Bridge Line to New England and Canada".



Accurail's HO scale kit for a Grand Trunk Western 40' wood refrigerator car with ice roof hatches is decorated with the distinctive GT wet noodle logo introduced in the early 1960s.



This 40' Milwaukee Road rib-side boxcar is based on a prototype built in December 1943 with double sliding doors. All Accurail HO car kits include Accumate couplers and appropriate trucks with Delrin wheelsets. For additional information contact a dealer or visit www.accurail.com.

Athearn has posted its production schedule for May 2022, and at the top of the list are Genesis HO scale models of Union Pacific 4-8-4 FEF-2 steam locomotives.



Models in two-tone grey representing UP locomotives in service from 1947-1952 will feature drop couplers, and dual smoke stacks. Both Armour Yellow and grey lettering will be available.



Post 1952 versions with smoke lifters and multiple stacks will be painted in solid black.



MAY HO SCALE NEWS | 6




Also coming next May is another release of Genesis SD60M diesel locomotives. Road names include three Conrail units. Spotting features of CR's SD60Ms are red marker lights on each end to support reverse movement and helper service.



Buffalo & Pittsburgh purchased several ex-Conrail SD60Ms in 2020. Athearn will offer B&P locomotives numbered 3887, 3889, and 3890 with number specific details.



After the breakup of Conrail, CSX acquired 30 ex-CR SD60M locomotives. Athearn's CSX models will be decorated in the YN3 scheme while retaining the CR-specific details.



Union Pacific SD60Ms in this release will be available decorated as-delivered, as well as in the post-2018 flag scheme. A Genesis SD60I decorated for Terminal Railroad Association will be included in this production run.



Introduced in the early 1970s, EMD's 3,000hp GP40-2 quickly became a popular replacement for first generation diesels. A significant feature of the GP40-2 was the introduction of the Dash 2 modular electrical cabinet.



Athearn has included an HO scale GP40-2 diesel unit in its May 2022 production schedule. Road names will include Seaboard System and three Chessie System units.

MAY HO SCALE NEWS | 7



Two road numbers for Ferromex will be in the May 2022 release along with Ferrocarril Chihuahua Pacifico No. 3019.



Three road numbers of a Canadian National GP40-2L (light frame) are included in this run. Canadian-specific details include a wide cab with four front windows, snow shields, and three-color classification lights.



Ex-CN GP40-2Ls will be available decorated for Indiana Harbor Belt and TPW-RailAmerica.



Athearn's Genesis SD60M, GP40-2 and FEF models in the May 2022 release will be available for DCC operation with an onboard SoundTraxx Tsunami2 sound decoder. DC models will feature QuickPlug technology with a 21-pin NEM connector for installation of an aftermarket DCC decoder.



HO scale versions of Thrall high side gondolas coming from Athearn next May will include a removable coal load. Seven decorating schemes will be available including Burlington Northern, David J Joseph Company, Western Electric, Zeigler Coal Company, Lake Erie, Franklin & Clarion, and two Herzog schemes.



Features on Athearn's Ready-to-Roll models include wire grab irons, and 100-ton trucks with 36" machined metal wheels.




Also coming from Athearn next May is a group of 40' steel boxcars fitted with Superior sliding doors.




Road names will be T&NO-Southern Pacific, Great Northern, Louisville & Nashville, Boston & Maine, Rutland, Erie

Lackawanna, and New Haven.



included in Athearn's May 2022 production schedule.

An HO scale 57' mechanical reefer, based on a prototype introduced by Pacific Car & Foundry in the 1960s, is



Road names include Tropicana, Santa Fe, Erie Lackawanna, Northern Pacific, Pacific Fruit Express, and NRRX-Cold Train.



New intermodal equipment coming from Athearn next May includes a group of 53' CIMC corrugated containers with a horizontal rib front. The containers will be available in 3-packs with different numbers for XPO

Logistics, JB Hunt, CSX, Hub Group, and Railpool.



Intermodal chassis will be available decorated for Pacer StackTrain, BNSF, CSX, Seacastle, JB Hunt, and Canadian National.



Roundhouse brand models coming from Athearn next May include a 34' twin-bay open hopper car with offset sides.



Road names will be Chesapeake & Ohio, Great Northern, Pittsburg & West Virginia, B&O Chessie System, and two schemes each for Santa Fe

and Cambria & Indiana. For additional information contact a dealer or visit www.athearn.com.



The latest production run of **Atlas** HO scale Gunderson 89' Multi-Max auto racks has been released to participating dealers.



Atlas' HO scale Master Line model replicates the Multi-Max concept introduced by the Greenbrier in 2013. The innovative design allows for changing the car from a Bi-Level to a Tri-Level, and back, without adding or removing decks.



Road names on this production run include Canadian Pacific, BNSF, Utah Central, Kansas City Southern, and two TTX schemes.



Also just released to dealers is an HO scale 36' wood refrigerator car. The Atlas Master Line model is based on a series of cars General American Car Company built in the mid-1920s for Cudahy Packing Co.



Features include opening doors and two different styles of opening roof ice hatches. The grab irons, ladders, stirrups, and door hardware are all separately applied.



Road names in this run include Agar Packing, Dold, Lange Creamery, Nuckoll's Refrigerator Line, New York Despatch, Pittsburgh Provision & Packing, Rex Canned Meats, and Schwarzschild &

Sulzberger. The factory is sold out of both the Multi-Max auto racks and the 36' wood reefers. Contact a dealer for availability.



Amtrak ALC-42 Charger #301 in its "Day 1" Heritage Livery. The model will include TCS WOWSound for sound, speed, direction, and lighting control, directional headlights, interior corridor work lights, marker lights, and ditch lights.

Bachmann has announced they will be releasing an HO scale model of

Bachmann has released an HO scale 250-ton steam crane and boom tender set to its dealers. The

ready-to-run model features a positionable boom and cab that swivels 360 degrees.



Road names are Santa Fe, Canadian National, Chesapeake & Ohio, Delaware &

Hudson, Pennsylvania, Reading, and a generic MOW. A painted but unlettered set is also available.



The crane rides on six-wheel trucks while the tender comes with arch bar trucks. Both truck types are molded in Celcon and are

equipped with blackened metal wheels with non-magnetic axles.



Bachmann has added new decorating schemes to its selection of HO scale truss-rod era tank cars. In addition to Union Tank Line, road names currently available include Blue Bell

Kerosene, Wheeling & Lake Erie, Philadelphia & Reading, U.S. Military, and New York Central.



The ready-to-run model features arch bar trucks with blackened metal wheels.



Quaker State, Texaco, and Ambrose Wine have been added to Bachmann's lineup of 40' triple dome tank cars.

Triple dome cars decorated

for Allegheny Refining, British American Oil, Pennsylvania Railroad, Protex, Shell, Transcontinental Oil, and UTLX all continue to be available.

Bachmann's HO scale Silver Series ready-to-run models feature appropriate Celcon trucks with blackened machined metal



wheels. For additional information contact a dealer or visit www.bachmanntrains.com.




Bowser is booking reservations for a January 2022 release of a large selection of 40' 70-ton triple-

bay hopper cars. The run includes cars with both 12 and 13 side panels. PRR class H39 cars with 12 panels will be available with the Pennsylvania name spelled out. One H39 hopper with arched ends will be available.



The third Pennsylvania class H39A car in Bowser's January release will have block PRR

lettering and Crown trucks.



Other road names for the 12 panel cars include Norfolk Southern, Canadian National,

Chesapeake & Ohio, Conrail, C&O/CSX, Erie Lackawanna, Louisville & Nashville, Penn Central, Southern Railway, and Denver & Rio Grande Western.



Bowser's class H37B coal hoppers, as built in 1958 with 13 side panels, will be available decorated for Penn Central and with simplified PRR block lettering.



Completing this production run of 13-panel hoppers is a class H37B car with



Pennsylvania spelled out. It will come with prototypically correct Crown trucks.



Bowser also announced Wabash National 53' RoadRailers in

several variations and paint schemes. The ready to run model includes pad printed ends, sides, mud flaps, and silver roofs. Versions include Platewall, Dura Plate, and Rivet Side trailers with an assortment of Norfolk Southern and Conrail Triple Crown schemes and logos. For additional information contact a dealer or visit www.bowser-trains.com.



R. Bale

UNION PACIFIC CHALLENGER

The Union Pacific's search for a powerful freight locomotive that could handle the mountain grades of Utah and Wyoming at high speed without the need of helpers, was finally fulfilled in 1936 with the development of the 4-6-6-4 Challenger. Unlike a Mallet compound locomotive that recycles the exhaust of one set of high-pressure cylinders into larger low-pressure cylinders, the Challenger 4-6-6-4s built by the American Locomotive Company were simple articulated locomotives with both front and rear engines using high-pressure steam directly from the boiler. Although built for freight service, the Challengers had 69" drivers, a large size usually reserved for high-speed passenger locomotives. While unheard of on other railroads, operating articulated steam locomotives at speeds at 60 to 80 mph was routine on the Union Pacific. R. Bale.



REGISTER
(free)


[INDEX](#)

[TABLE OF CONTENTS](#)

MRHMAG.COM

[INDEX](#)

[TABLE OF CONTENTS](#)



Broadway Limited has set a fall 2021 delivery date for an HO scale model of a Union Pacific 4-6-6-4 Challenger steam

locomotive. The BLI model represents the class CSA-2 series of Challengers as they appeared post-1947. The locomotive superstructure and tender body are brass mounted on diecast chassis.

BLI will offer three variations of the CSA-2 Challenger: with the front engine as-delivered, with the front engine rebuilt, and with the front engine cast with integral cylinders. Each version will be available both fully decorated and painted but unlettered. A limited number of models will be available either varnished brass or painted brass.



Broadway Limited and its authorized dealers are accepting reservations for a Milwaukee Road 4-8-4 class S3 steam locomotive.

The HO scale model is based on ten S3 class 4-8-4 locomotives the American Locomotive Company built in 1943-44. The prototypes were used in both freight and passenger service during the ten years they were operating.



The superstructure, chassis and tender of BLI's HO scale model are die-cast metal. In addition to standard black service

paint, BLI will offer the model in a 1935-era fantasy Hiawatha scheme. A painted, unlettered version will also be available.

The electronic package in BLI's 4-6-6-4 and 4-8-4 models features Paragon4 sound and control system, built-in capacitor pack for uninterrupted electrical pick-up, synchronized smoke and variable exhaust chuff, and golden-white LED head and rear lights.




Just announced by BLI is the Pennsylvania RR I1sa 2-10-0. The I1sa was a modification of the I1s Decapod with an increased maximum speed cut-off, which increased low-

speed tractive effort. A total of 489 I1s locomotives were upgraded to the I1sa type. BLI is offering three variations of the I1sa: with the original headlight position and a short 90F82 tender, with a modernized headlight position and the 90F82 tender, and with the modern headlight and a long-haul 210F82A tender. A painted but unlettered version of the original headlight and 90F82 tender version will be available. The HO scale model will feature Paragon4 sound and DCC.



Also announced is an HO scale model of the EMD SD40-2 featuring Paragon4 sound and DCC, a precision

drive mechanism engineered for heavy towing and smooth slow speed operation, all-wheel electrical pickup, 5-pole skew-wound can motor, ABS plastic body with a die-cast chassis, separately applied detail parts such as handrails, grab irons, fans, sunshades, and antennas, and metal Kadee-compatible couplers. Roadnames in this release include Santa Fe, BC Rail, BNSF, CNW, CSX, Family Lines System, Illinois Central, Ontario Northland, RCPE, RBMN/Reading and Northern, UP, and undecorated. For additional information contact a dealer or visit www.broadway-limited.com.




The **Chesapeake & Ohio Historical Society** is selling 3D printed HO scale lineside details including whistle posts, clearance posts, mile posts, cross bucks and phone boxes. Individual cross bucks are available that replicate

variations in Virginia, Indiana, Kentucky and West Virginia/ Ohio locations. The items are accurately scaled from C&O documents. For additional information visit the Chessie Shop at chessieshop.com.




The **Electric Wallpaper Co.** has released a Roomettes laser-cut cardstock kit to fit Walther's HO-scale Row House building. The Roomette Spruce Street Row House (04-933-3778) includes seven rooms for the Walther's model including generic bedrooms that can be placed in a number of locations.



Walther's Import Motors structure can be significantly enhanced using Roomettes Broekema Auto Sales interior. The Roomettes laser-cut interior kit offers two rooms and three LEDs, as

well as a variety of additional details including a sales counter, tool chests, vending machine, posters, banners and exterior

signs. Flag streamers are included for the exterior parking lot. This kit creates a realistic scene for displaying exotic motor cars. The kits include LEDs with plugs that are compatible with lighting systems from Woodland Scenics JustPlug, Model Train Technology and NCE.



A new idea from The Electric Wallpaper Co. are interiors for HO scale rolling stock. The initial release includes

an interior for Atlas's 60' auto parts boxcar in both single- and double-door configurations. Also new is an interior kit for an Athearn 'Blue Box' double-door Railbox car. For additional information visit www.roometteslighting.com.



R. Bale

DROP-BOTTOM GONDOLAS

The idea of a flat bottom gondola with doors that could be opened to assist in unloading was introduced in the early 1900s. Unlike hopper cars, drop-bottom gondolas could be kept busy hauling lading such as lumber, steel and pipe when not in coal service. Drop-bottom gondolas generally had 12 to 16 bottom doors that discharged 90 to 95 per cent of the car's load to each the side of the tracks. Since the cars were not entirely self-cleaning, laborers with shovels were required to clear anything remaining in the car. The door opening mechanisms were operated in sets of four (two per side) by actuating rods visible just below the side of the car. Some drop-bottom cars in ballast service could discharge to the center of the tracks. Drop-bottom gondolas ranged from 40' to 42' in length. Most were all-steel but some were of composite construction using both steel and wood. Since some of the doors were located above the trucks, the body of drop-bottom gondolas was somewhat higher than the usual gondola car. The addition of side extensions allowed the cars to be used for low density lading; notably wood chips and sugar beets.





InterMountain plans to release two styles of HO scale 41' general-service drop-bottom gondolas this summer.

Multiple road numbers will be available for eight-panel all-steel gondolas decorated for Great Northern, Southern Pacific, Denver & Rio Grande Western, and Union Pacific.



Steel drop-bottom gondolas with board side extensions for wood chip service will be available for Western Pacific and Spokane, Portland & Seattle.



A Southern Pacific composite gondola with wood sides and an exterior steel frame in a Pratt truss will have plywood side

extensions designated for beet service. All versions of the InterMountain drop-bottom gondolas will have solid-bearing trucks with 33" metal wheels.



InterMountain also plans to release an HO scale version of the distinctive 59' 4550 cu. ft. cylindrical Canadian grain car this summer.



Between 1972 and 1985 the Canadian government built nearly 20,000 of the prototypes to assist the

Canadian rail system in transporting huge quantities of grain.




Over the years many American grain carriers acquired and operated similar cars in the U.S.



Road names in this release will be CNWX-Canada (red), ALNX-Alberta with "Take an Alberta Break" slogan, CNWX-Canadian

Wheat Board, Ferrocarriles Nacionales de México, and an ex-Koppel car patched for Santa Fe.



Features on InterMountain's HO scale version include etched-metal roofwalks, appropriate trucks with metal

wheelsets, and knuckle couplers. The trough hatches will be smooth, parallel ribbed, or round depending on the practice of the prototype being modeled. For additional information contact a dealer or visit www.intermountain-railway.com.



R. Bale

OFFSET-SIDE HOPPER CARS

The idea of increasing the capacity of a hopper car by placing the sheet metal sides outside the vertical side posts was proposed in the mid-1920s. The design significantly increased the cubic capacity of an outside-braced car of otherwise similar dimensions. After considerable testing the ARA adopted two designs in 1928: a 40' 70-ton car with four hoppers, and a 34' 50-ton triple-bay car. Three hoppers on a 34' car quickly proved to be redundant and ARA/AAR subsequently approved a car with just two discharge bays. In rotary dumping offset-side cars suffered from rivets pulling out because the side sheets and vertical support posts were under tensile forces rather than compressive forces in straight-side cars. In addition, vertical posts placed inside the car were more prone to corrosion than posts outside of the car. The attraction of offset-side cars began to fade in the 1960s as the coal-hauling industry moved to larger cars of greater capacity.



Kadee's latest release is a 50-ton AAR twin-bay open hopper car decorated for ATSF. The model represents a prototype with offset sides built for the Santa Fe in

1948. The HO scale ready-to-run model comes with a removable lump-egg coal load. The model features Kadee self-centering equalized trucks and Kadee metal knuckle couplers. For additional information contact a dealer or visit www.kadee.com.



Menards is selling a fully assembled and detailed model of a FedEx distribution building. As shown the HO scale structure is 3" tall. It has a footprint of 6.625" x 3.312". The structure is decorated with 15 LED lights which require a

4.5 volt power supply that is sold separately. For additional information visit www.menards.com/trains.



National Scale Car is selling a Mini Kit that converts an InterMountain model to a Southern Pacific 84340 series (or its subsidiary Texas & New Orleans 54100 series)

1937 ARA boxcar with Superior sliding doors and Union Duplex fixtures and tracks. Mini Kit MK102.1 contains a pair of 10' IH 6' wide Superior resin doors, etched door tracks, accurate Speedwitch decals and instructions. The modeler must supply an Intermountain 1937 ARA boxcar. For additional information visit www.nationalscalecar.com.



Heading a list of new 1:87 scale vehicles available from **Oxford Diecast** is a 1957 Chevrolet Nomad decorated in Surf Green over Highland Green.



Also new are a 1968 Dodge Charger R/T in black over gold and a 1936 Buick Special convertible. Completing Oxford's list of new releases is a 1965 Chevrolet Stepside pickup truck. For additional information contact a dealer or visit www.walthers.com.



Piko-America has scheduled an August release for an HO scale model of a 65-ton Whitcomb diesel locomotive as used by the United States Army Transportation Corps.

Built in America during WWII, Whitcomb designed the locomotives, also known as the 65-DE-19A, to handle the tight clearances of European railroads. Following the war, some of the locomotives returned to serve on industrial short lines across America. The model will be available without sound and with a PIKO 4.1 SmartDecoder and sound. For additional information contact a dealer or visit www.piko-america.com.



Rapido is booking orders for a model of a Southern Pacific B-100-40 boxcar as built by Pacific Car & foundry in 1976.

Finite details on Rapido's HO scale version include a Hydra-Cushion underframe, 12' plug-doors, Car Pac loaders, and the unique half-height waffle sides.




Additional features include separately applied metal grab irons, full underbody brake rigging, separate door rods and door tracks, and Kadee couplers. Rapido has tooled new trucks with 36"

machined metal wheels for this model.



In addition to the original Southern Pacific scheme, road names will include Golden West-Ventura County, Golden

West with an SP Patch, Columbus & Greenville, and Southern Pacific/Union Pacific repaint with a three-color shield.



Cars decorated for Amtrak will be available in green and in Amtrak's Phase IV scheme. An undecorated model will

also be available. For additional information contact a dealer or visit www.rapidotrains.com.




R. Bale

EMD SD45 LOCOMOTIVE

Beginning in the early 1960s America's railroads began shopping for high horsepower locomotives that could accelerate fast and maintain high speed for an extended period. EMD's answer was the SD45, a 3,600hp beast built around a huge 20-cylinder prime mover. The imposing six-axle SD45 introduced the distinctive concept of flared radiator intakes at the rear of the body. Numerous railroads bought the SD45, but the early success of the locomotive faded as the massive 20-cylinder prime mover revealed a tendency to break crankshafts. EMD came up with a fix to the problem, which was attributed to engine block flex; but the SD45's reputation had been severely damaged. Known as a fuel guzzler, the SD45's reputation was further harmed as fuel prices soared in the 1970s.

ScaleTrains.com is booking reservations for an HO scale Rivet Counter model of an EMD SD45 locomotive. Availability is planned for December 2021.




Road names on this run will be Southern Pacific, Penn Central, Erie Lackawanna, Lackawanna

Bicentennial, Norfolk & Western Bicentennial, and Pennsylvania Railroad. A high nose version of the SD45 will be available decorated for Southern Railway and VMV Leasing (ex-Southern).



ScaleTrains.com's Rivet Counter SD45s feature numerous road and road number specific details.

Features common to all road names include detailed cab interior with separate floor, rear wall, seats, and standard AAR control stand, sliding cab windows, inertial air intake grilles, accurately profiled dynamic brake housings, see-through dynamic brake intakes with resistor grid, wire grab irons and lift rings, individual windshield wipers, horns, coupler cut levers, trainline hoses, and metal Type E knuckle couplers.



Electrical features include LED directional headlights, printed and LED-lighted number

boards, and all-wheel electrical pick-up.



ScaleTrains.com's SD45s will be available for standard DC operation (DCC ready with 21-pin


connector), and with an ESU Loksound DCC decoder with two capacitors.

ScaleTrains.com has released an HO scale model of a Thrall-Trinity 42' coil steel car. More than 130 individual parts go



into assembling this ready-to-run Rivet Counter model. Features include a removable hood, see-through photo-etched metal walkway, simulated wood

interior floor, positionable load dividers, complete underbody brake details, and a coil steel weight load. Road names currently available are Norfolk Southern, CSX, Ferromex, and Kansas City Southern.



ScaleTrains.com has scheduled a mid-November 2021 release date for another production run of its GATC 4180 cu. ft. Airslide covered

hopper. The HO scale ready-to-run model replicates a popular Airslide prototype with gravity outlet gates built over a five year period beginning in 1969.

The Rivet Counter model will be available with road specific details for seven paint schemes. Champion Spark Plug car 47776 replicates a prototype built in 1977 with a Morton walkway. The four other Champion cars in this release represent prototypes built with Apex steel walkways in 1969.



GACX Blue car 47754 has conspicuity strips and a Morton walkway. Other Blue cars will come with Apex walkways.



Cars decorated for Brach's Candy and for Staley will have Apex steel walkways. American Maize cars will have a combination of Apex and

Morton walkways. All of ScaleTrains.com's Airslide cars decorated for Church & Dwight will have Morton walkways.

Features on all versions of the Rivet Counter model include metal grab irons and coupler cut levers, trainline hoses, underbody brake details including formed wire plumbing and brake rods, diecast metal Type E knuckle couplers, and Barber S-2 100-ton trucks with raised foundry data, 36" machined metal wheels, rotating bearing caps, and truck-mounted brake beams.



ScaleTrains.com is planning to release another production run of PS-2CD 4785 cu. ft. triple-bay covered hopper

cars in December. Road names will be Conrail, CSX, Burlington Northern, Staley, Monfort-TLCX, Hubinger/TLCX, Penn Central, Boyll & Son/TKDX.



Highlights of the HO scale Rivet Counter model include numerous variations in roof hatches, outlet gates, roof

walks, and end cage support details. For additional information visit [scaletrains.com](https://www.scaletrains.com).



Tangent has released a new HO scale Pullman-Standard PS-1 boxcar with combination doors. The model accurately replicates unique prototypes purchased by

three western railroads. Combination door cars built for Milwaukee Road have a 15' 2" door opening fitted with a 7' 2" plug-door on the left and an 8' Youngstown sliding door centered on the car side.



A Northern Pacific variant has a 14' opening with a 6' sliding door in the center and an 8' plug-door on the left. A unique version

modified by the Union Pacific has a door arrangement similar to the NP car. They were rebuilt from early PS-1 production that had a different roof and ends. UP also added a large side sill and a lumber loading door on the A end. All of these variants are included in Tangent's model of the UP car.



The UP and Milwaukee Road models come with 50-ton Barber S-2 solid-bearing trucks. The NP car has 50-ton ASF A-3 Ride Control roller-bearing trucks

with rotating Timken bearing caps. Both types of trucks have 33" machined metal wheelsets

Notable details on all versions of the Tangent model include Kadee couplers, Pullman-style ladders and grab iron brackets, rubber air hoses, and see-through running boards and brake steps. Variable details depending on the prototype being modeled include two types of PS-1 ends, Equipco or Ajax brake housings, and Equipco, Ajax, or Universal brake wheels.

Undecorated kits are available for each of the three version of the PS-1. For additional information visit www.tangentscalemodels.com.



R. Bale

EMD SW7 SWITCHERS

EMD (Electro-Motive Division of General Motors) introduced the SW7 switcher in October 1949. Powered by GM's 1,200hp model 567A V12 prime mover, the SW7 was an upgrade to EMD's 1,000hp NW2 switcher. Although it shared the same 44' 5" chassis, B-B trucks and similar body of its NW2 predecessor, the SW7 had a few distinguishing features including square front cab windows, dual headlights, and a full-height front radiator grille. With the exception of similar, minor modifications, EMD's NW2, SW7 and subsequent SW9 and SW1200 locomotives were nearly indistinguishable. Collectively they represent a successful design that sold well over 3,000 units.




Walthers plans to release an HO scale model of an EMD SW7 diesel switch locomotive late this month. The Walthers Mainline series model is based

on Phase II production units built in 1950-51.




Identifying details include a large front radiator with wire grille cover, dual sealed beam headlights, letter board gap in louvered

side doors, square center cab windows, and dual conical exhaust stacks.




Road names on this release will be Atlantic Coast Line, Chicago, Burlington & Quincy; Detroit & Toledo Shore Line, Illinois Central

Gulf, New York Central, and Union Pacific.



Walthers HO scale SW7 will be available for standard DC operation and with factory installed ESU Sound and DCC decoder.



Walthers has released a Cornerstone kit for an HO scale Municipal Water Tower. The kit is molded in gray plastic with steel guy wires. Lettering decals are included. The assembled tower measures 11.125" tall by 3.32" square.


Walthers is quoting a late June release for an HO scale lighthouse with a flashing LED light. The Cornerstone kit requires no painting as the individual parts are molded in

appropriate colors. The assembled model is 8.87" tall and has a foot print of 8.125" by 3".



Walthers is taking reservations for three new HO scale

modern highway overpasses. The first is a steel and concrete overpass with pipe railings, the second a concrete overpass with concrete sides, and the third a steel overpass with concrete sides. All three kits include round and square support columns in two heights, can be built as single or double span, and come with detailed abutments. The kits are expected in late May 2021. For additional information contact a dealer of visit www.walthers.com.




ZYX Creative is selling an HO scale tunnel portal based on the east portal of tunnel number 21 on the Southern Pacific Shasta Division in the Oregon Cascades. The 3D printed resin model features raised concrete form lines, a set of utility boxes that can be attached to the tunnel face, a 1925 date stamp, and paper printed

tunnel numbers. The model is available reversed with the long wall on the right. Liners are also available separately. For additional information visit www.zyxcreative.com/tunnels.

N SCALE PRODUCT NEWS

Athearn's May 2022 production schedule includes two new N scale models including a 57' mechanical reefer.



The model is based on a prototype introduced by Pacific Car & Foundry in the 1960s.

Road names include Tropicana, Santa Fe, Erie Lackawanna, Northern Pacific, Pacific Fruit Express, and NREFX-Cold Train.

New N scale intermodal equipment coming from Athearn next May includes a group of 53' CIMC

corrugated containers with a horizontal rib front. The containers will be available in 3-packs with different numbers for XPO Logistics, JB Hunt, CSX, Hub Group, and Railpool. For additional information contact a dealer or visit www.athearn.com.



R. Bale

GP40 LOCOMOTIVE

In 1966 Electro Motive Division introduced the GP40, a new four-axle road switcher powered by a 16-cylinder 645-series prime mover. Although similar in appearance to its GP35 predecessor, the new GP40 was distinguished by three large 48" radiator fans at the rear of the locomotive body. Between 1966 and 1971 EMD produced more than 1,221 GP40s including 60 units built with high-short-hoods and dual control stands for the Norfolk & Western Railway. On January 1, 1972, the GP40 was discontinued and replaced by the GP40-2, which has a modular electrical system and a few minor exterior changes.



Atlas N scale models available now from participating dealers include a new production run of GP40 diesel locomotives.




Popular road names just released with new road numbers include NJ Transit, Milwaukee Road, Southern Pacific, Western Pacific and Canadian National.



New road names include Detroit, Toledo & Ironton; Baltimore & Ohio, RF&P, and Montana Rail Link. The N scale locomotives are available for standard DC operation as well as with an ESU sound DCC decoder.



Also just released to Atlas dealers is a group of articulated auto carriers. The N scale model is based on a prototype introduced by Thrall in 1997.



Features of the Master Line model include a weighted diecast chassis, an articulated diaphragm, end door details, and 70-ton roller-bearing trucks. In addition to Santa Fe, road names are TOAX, BTTX, and two Norfolk Southern schemes.



Atlas has included an NE-5 steel caboose in its spring release to dealers.



Road names of the N scale Master series model include Boston & Maine, Chicago Great Western, Chicago & North Western; New Haven, Penn Central, and Wisconsin Central. Contact a dealer for availability.



Broadway Limited plans to release two N scale versions of an early EMD switch engine next month. EMD 1,000hp NW2 switchers will be available decorated for Southern Pacific, Boston & Maine, Chicago, Great Western, Chicago & North Western, Erie-Lackawanna, Milwaukee Road, Pennsylvania Railroad, and Union Pacific.



EMD 1,200hp SW7 switchers will be available decorated for C&O Chessie System, Atlantic Coast Line, Detroit & Toledo Shore Line, Southern Railway, Great Northern, Maine Central, Pennsylvania Railroad and Union Pacific.

Special features available on both versions of the EMD switcher include Paragon4 sound and control with Rolling Thunder, and a default switcher mode for slow speed control.

Also announced is the EMD SD40-2 in N scale, with both high-hood and low-hood variations. Equipped with Paragon4 sound and DCC for slow speed operation in DC and DCC, the model





features all-wheel pickup except on traction tire equipped wheels, separately applied parts such as handrails, grab irons, horn, bell, and cut levers; separately controllable headlight, rear light, and ditchlights; and Micro-Trains compatible couplers.



Roadnames in the 2021 production include low hood models decorated for BHP, BNSF, CP, CSX, Florida East Coast, Milwaukee, Missouri Pacific, UP, and undecorated. High hood models will be available for CP Rail, Norfolk & Western, Norfolk Southern, and Southern. For additional information contact a dealer or visit www.broadway-limited.com.



Eastern Scale Models will be releasing an N scale laser-cut enhancement kit for the Wheels of Time 53' flatcar. The kit, #990203, consists of five plywood deck parts and two bolster top assemblies. Availability is later this quarter. For more information visit www.esmc.com.



InterMountain is selling an N scale 4750 cu. ft. triple-bay covered hopper with rib sides in 25 different paint schemes.

Railroad road names are BNSF (Circle cross round logo), Burlington Northern, Delaware & Hudson, Illinois Central Gulf, Kansas City Southern, Santa Fe "Q", Union Pacific (three color




shield), and Union Pacific Bicentennial.



Cars decorated for lease operators include ACOX-Aurora Co-op, BLMR-Grain Train, GNBX-Farmrail "I Care" series, NAHX-Big 6 Coop, NAHX-Cook Industries, NAHX-Dawson Soy Products, NAHX-Goodseed & Grain, NAHX-Lapeyrouse Grain, and NAHX-West Bend Elevator.



Completing the list of leased 4750 cu. ft. covered hoppers are PLCX-NEW Cooperative, PLMX-Grain Handling Corp., PTLX-Sand's of Iowa, PTLX-Allied Mills, PTLX-Farmers Elevator, PTLX-Pomeroy Co-op Grain, PTLX-State Line Elevator, and USLX-Evergreen Fish Hatchery. Each car is available in multiple numbers.



The N scale models feature etched-metal roof walks, operating knuckle couplers and trucks with machined metal

wheelsets. For additional information contact a dealer or visit www.intermountain-railway.com.

Did you see this article?



A Brit models 1860s Georgia railroading

Get the May eBook now

← click here

In **MRH** **RUNNING** **EXTRA**






R. Bale



BETHGON/COALPORTER GONDOLAS

Developed in the late 1980s by Bethlehem Steel Company – with follow up work by Johnstown America and Freight Car America – the BethGon has become one of the most common cars for hauling coal. The

BethGon design added 15 to 18 additional tons of coal carrying capacity by replacing moving hopper doors and high-maintenance locking mechanisms with long tubs on either side of the cars center-sill. In 1997, Conrail built 600 BethGons using construction drawings supplied by Johnstown America. These were 4,100 cu. ft. cars with a capacity of 116 tons of coal. As the nation's demand for coal lessened, BethGons have been repurposed to haul biodegradable animal feed which required the application of a protective tarp. Note: Originally called the CoalPorter, the name was changed to BethGon when the family of composer Cole Porter asked Bethlehem Steel to come up with an alternate name.



car loaded or empty. The interior bracing has been replicated so the details show when the car is operated without a load.



Norfolk Southern, and Union Pacific.

KatoUSA is selling an N scale BethGon gondola with a removable coal load that allows operators to run the

Kato has modified its original BethGons with a cap that represents a rolled-up tarp.

The cars are sold in eight-car sets for the following road names: CSX, BNSF (Swoosh), Canadian National,



Kato is selling an N scale version of the very successful SD40-2 diesel locomotive EMD produced for 14 years beginning in 1972.



The Kato model represents mid-production units with post-1990 road specific details such as placement of ditch lights, horns, and air conditioning equipment.



Road names are Santa Fe, Burlington Northern, and Norfolk Southern in the colorful Maersk scheme. The models are available for standard DC operation and with Digitrax or ESU LokSound

DCC. For additional information contact a dealer or visit www.katousa.com.




New N scale models from **Micro-Trains** include two versions of a heavyweight RPO (Railway Post Office) car. A

Denver & Rio Grande Western version of the RPO is decorated in Pullman green with gold lettering. It rides on 4-wheel Commonwealth passenger trucks.



A second RPO from Micro-Trains, which has 6-wheel heavyweight passenger trucks, is decorated in Chesapeake & Ohio's tri-color scheme.



This 50' D&RGW boxcar is based on a prototype built by PC&F in the mid-1960s. Spotting features include an 8' plug-door, shortened ladders, and no running board.



Pullman-Standard built the prototype that inspired the N scale version of this Illinois Central 40' hi-cube boxcar. Its 4,900 cu. ft. capacity was designed to handle bulky appliances.



NATX leased this 39' single dome tank car to the Hubinger Co. of Keokuk, Iowa, for transporting corn syrup.



Micro-Trains N scale version of a standard 50' St. Louis-San Francisco Railway boxcar features 8' plug-doors, short ladders and no running board. For additional information on these models including availability contact a Micro-Trains dealer.



RailSmith plans to release two N scale Southern Pacific lightweight Cascade coaches by mid-summer. A few reservation slots for these models were still open at press time.




More two-tone gray Cascade cars will be arriving later this year including three newly-announced 1950-era 10-6 sleepers. The three cars include SP numbers 9032 and 9033 and Northern



Pacific number 364.



RailSmith is accepting advance orders for The Texas Special heavyweight 12-1 sleeper McCallsburg. Availability is expected at the end of 2021 or early 2022.



RailSmith is also booking reservations for PRR's yellow Buffalo Rapids, one of the lightweight ACF-built 10-6 sleepers Pennsy assigned to interline service on various trains including UP's Overland and City of San Francisco. For additional information visit lowellsmith.net.



R. Bale

PROCOR 20,000 GALLON TANK CAR

Products Tank Line of Oakville, Ontario (renamed Procor in 1962), developed a line of standard design tank cars in the 1960s that established standards for a new generation of modern equipment. The GP20 (general purpose 20,000 gallon) tank car was ideal for lighter density commodities such as various oils and fuel that would not congeal or freeze in cold weather. The GP20 was also available with interior heater coil pipes to stabilize temperature sensitive products. It was available with either 70-ton or 100-ton trucks. Later designs were also available with a specialized dome that allowed the tank rating to be upgraded from 60 psi to 100 psi. The standard GP20 design was manufactured from 1969 through 1984. When production of the car ended Procor had built almost 1,000 cars of the standard GP20 design. GP20s continue in service across North America in both fleet and lease service.



REGISTER
(free)


[INDEX](#)

[TABLE OF CONTENTS](#)


MRHMAG.COM

[INDEX](#)


[TABLE OF CONTENTS](#)



Rapido has announced plans to produce a fully detailed N scale version of a Procor 20,000 gallon GP20 tank car.



The model is being developed using original Procor blueprints and engineering data.




Details will include photo-etched metal walkways, detailed vent stacks, loading hatches, and complete underbody and brake equipment.




Road names on the initial release will include UTLX, UTLX-Alberta Government, PROX, NCTX, CP Rail, BC Rail, and undecorated. For reservation information contact a dealer or visit www.rapidotrains.com.

NEW DECALS, SIGNS AND FINISHING PRODUCTS

Archer Transfer has introduced a resin raised surface decal that simulates the retaining clips on steel gondolas cars. The retaining clips are based on material researched by master prototype modeler Frank Hodina. The new decal is available in



HO, S and O scales. For additional information visit www.archertransfers.com.



Great Decals has released several new water slide decals including an HO scale set for Southern Railway MOW Hi-Railer truck, pickups and speeders. The lettering set includes "The Southern" and "Southern

Railway" logos with and without "Look Ahead-Look South" in black/clear, green/clear and green/yellow.



Also new from Great Decals is an HO scale lettering set for Southern Railway Greenville 100-ton brown aggregate hopper cars. The set includes white lettering, ACI panels and black lube plates. This set includes the Southern road name, road numbers, capacity data, and multiple numbering options. The set will decorate two cars. For additional information visit www.greatdecals.com.

National Scale Car has released two new HO scale decal lettering sets of interest to prototype modelers. NSC set D219 includes material to accurately decorate Western Pacific AAR standard design steel boxcars with an inside height of 9' 6".



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

MRHMAG.COM

[INDEX](#)

[TABLE OF CONTENTS](#)



NSC lettering set D220, which includes a three-color herald, will correctly decorate Lehigh New England ARA-design steel boxcars the road received in 1927 from Pressed Steel Car Co., and Magor Car. For additional information visit nationalscalecar.com.

DISCLAIMER

The opinions expressed in this column are those of the writer and do not necessarily reflect the opinion of Model Railroad Hobbyist or its sponsors. Every effort is made to provide our readers with accurate and responsible news and information, however, neither Model Railroad Hobbyist or the writer of this column can be held responsible for any inaccuracies or typographical errors that may inadvertently appear in this column.



RATE THIS ARTICLE



! BRIEFLY NOTED AT PRESS TIME ...

Atlas O is taking reservations for the initial run of 70' heavyweight passenger cars produced from tooling recently acquired from M.T.H. The cars will be available in single and multiple packs for B&O, GM&O, B&M, PRR, and U.S. Army. Details at shop.atlasrr.com/d-653-o-heavyweight-passenger-cars.aspx?mc_cid=d38d301df9&mc_eid=6bff0ec9ce ...

Bachmann has announced the availability of an N scale GP38-2 equipped with DCC Econami Sound decorated for BNSF, CSX, and UP. See a dealer for details ...

Dave's Decals has a new HO scale 1950s-era bottled soda dispensing machine with decals for 7UP, Brando, Coke, Dr. Pepper, Pepsi, and RC Cola. Details at www.davart.net ...

New from **Morning Sun Books** is Volume 3 of *The Monongahela Railway in Color: The Conrail and NS Era ...*

Resin Car Works has released prototypically accurate HO scale kits for a Louisville & Nashville 40' steel drop-bottom gondola, and a modified AAR 40' steel boxcar as owned by Duluth, South Shore & Atlantic; and Soo Line. Details at resincarworks.com ...

After several months of preparation **Woodland Scenics** has released to dealers its HO scale Utility System that includes ready-to-use power poles, power lines and substations... ■

Did you see this article?



No more ugly track cleaning cars

Get the May eBook now

← [click here](#)

In **MRH** **RUNNING**  **EXTRA**



SELECTED EVENTS



Model Railroad Hobbyist | May 2021

MAY

Due to COVID-19 restrictions, please check with any organization hosting an in-person event for the latest status of the event.

Ongoing 2021

ONLINE, Zoom, dates vary, see website. Operation Special Interest Group Meetups – limited attendance available. For more information visit www.opsig.org/Virtual Past meets are available online at www.opsig.org/Virtual/Past.

ONLINE, Zoom & YouTube, Wednesday & Saturday, see Facebook page. “New Tracks” Meetup, hosted by Jim Kellow, MMR. See newtracksmodeling.com for more information.

ONLINE, Facebook & YouTube, dates vary, see Facebook page. “NMRAX” organized by Gordy Robinson, Martyn Jenkins, Gert Muller, Jordan Kramer. See www.facebook.com/groups/nmraxgroup for announcements.

ONLINE, YouTube, every other Saturday. 4th Division, Pacific Northwest Region, NMRA hosts online layout tours and clinics. Archive available at www.youtube.com/c/4DPNRMovies.

ONLINE, Zoom, Second Tuesdays, 8pm EST. “Off the Beaten Track” featuring Narrow Gauge layouts, clinics and manufacturers. For more information visit groups.io/g/NNG.

SELECTED EVENTS | 43

May 2021

ONLINE, Zoom, May 21, 28, June 4, 11, Virtual Railway Modellers Meet of BC, sponsored by 7th Division, PNR, NMRA. For more information visit railwaymodellersmeetofbc.ca.

COLORADO, COLORADO SPRINGS, May 22, TECO Model Train Outdoor Swap Meet. Chapel Hills Mall, 1710 Briargate Blvd. For more information visit www.tecoshow.org.

INDIANA, FRANKLIN, May 15, Franklin Train Show, presented by the Central Indiana Division of the NMRA. Johnson County Fairgrounds. For more information visit www.cidnmra.org/services.

PENNSYLVANIA, KUTZTOWN, May 15. Renningers Model Train Meet, 740 Noble Street. For more information see renningers.net/events/model-train-meet.

TENNESSEE, NASHVILLE, May 30 – June 5, 2021. 36th National Garden Railway Convention, Gaylord Opryland Resort & Convention Center, 2800 Opryland Drive. For more information visit ngrc2021.com.

Future 2021-2022 by location

ONLINE, Zoom, May 21, 28, June 4, 11, 2021, Virtual Railway Modellers Meet of BC, sponsored by 7th Division, PNR, NMRA. For more information visit railwaymodellersmeetofbc.ca.

ONLINE, Zoom, CANCELLED, August 7th, 14th, 21st & 28th. Idaho Rails - Pacific Northwest Region, NMRA Regional Virtual Convention. For more information visit sites.google.com/view/3rddivisionpacificnorthwestreg.

CALIFORNIA, IRVINE, September 8-11, Pacific Southwest Region/NMRA Convention, “Orange Blossom Special.” Hilton Irvine/Orange County Airport Hotel, 18800 MacArthur Blvd. Visit www.psrconvention.org/OrangeBlossomSpecial2021 for more information.

CALIFORNIA, SANTA CLARA, CONVERTED TO VIRTUAL – July 4-11, 2021, Rails By the Bay, 2021 NMRA National Convention and National Train Show. Santa Clara Marriott Hotel. Efforts are underway to present the convention as a virtual convention online in. For more information visit www.pcrnmra.org/NMRA2021.

FLORIDA, MELBOURNE, June 5, September 4, December 4, Original Melbourne Train and Toy Show, sponsored by Schultz Space Coast Trains, Azan Shrine Center, 1591 W Eau Gallie Blvd. For more information visit schultzspacecoasttrains.com.

FLORIDA, TALLAHASSEE, June 26-27, 30th Annual Tallahassee Model Railroad Show and Sale, sponsored by Big Bend Model Railroad Association, 441 Paul Russell Rd. For more information visit www.facebook.com/events/745873359647741.

GEORGIA, CARTERSVILLE, October 2-3, 2021 Piedmont Division Model Train Show, Clarence Brown Conference Center, 5450 GA-20. For more information visit themodeltrainshow.com.

ILLINOIS, COLLINSVILLE (St. LOUIS), July 30-31, 2021. St. Louis Railroad Prototype Modeler's Meet. Gateway Convention Center, 1 Gateway Dr. For more information visit stlrpm.com.

KANSAS, HUTCHINSON, June 5-6, 2021, Center of the Nation Model Railroad Expo, Pride of Kansas Building, Kansas State Fairgrounds. For more information visit www.kansascentralmodelrailroaders.org/train-show.html.

MARYLAND, LINTHICUM HEIGHTS (BALTIMORE), September 10-11, 2021, Mid-Atlantic Railroad Prototype Modelers Meet, Doubletree by Hilton – BWI, 890 Elkridge Landing Rd. For mor information visit www.marpm.org.

MARYLAND, HUNT VALLEY, October 21-24, 2021, Mid-Eastern Region Convention – Mount Clare Junction Model Railroad – NMRA membership not required, Delta Hunt Valley, 245 Shawan Road, mtclarejct.com.

MASSACHUSETTS, WESTFORD, October 8-11, 2021, Mill City 21, the NER Convention. Westford Regency Inn, 219 Littleton Rd. For more information visit millcity21.org.

MISSOURI, St. LOUIS, August 7-14, 2022, NMRA National Convention and National Train Show.

NEVADA, ELY, June 25-26, Bristlecone Bricks & Train Show, Nevada Northern Railway Museum Freight Barn, 1100 Ave A. For more information visit bristleconebricks.com.

NORTH CAROLINA, HICKORY, September 1-4, 41st National Narrow-Gauge Convention, Hickory Metro Convention Center and Crowne Plaza Hotel. For more information visit 41nngc.com.

OHIO, TOLEDO, October 21-24, 2021. Black Swamp Junction – NCR 2021 Convention, hosted by the NMRA, open to all, featuring clinics, tours, layouts, op sessions, and door prizes. Radisson Hotel at the University of Toledo, 31100 Glendale, Ave. For more information visit www.divisiononencr.com/2021.

OHIO, VAN WERT, July 24-25, 2021, 18th Annual Van Wert Railroad Heritage Weekend Model Railroad Show and Swap. Van Wert County Fairgrounds, 1055 S Washington St. For more information visit www.vwrrhw.com.

PENNSYLVANIA, KUTZTOWN, July 17, August 28. Renningers Model Train Meet, 740 Noble Street. For more information see renningers.net/events/model-train-meet.

TEXAS, STAFFORD (GREATER HOUSTON), August 14, 2021, Greater Houston Train Show, Stafford Centre, 10505 Cash Rd. For more information visit sanjacmodeltrains.org.

TENNESSEE, NASHVILLE, June 15 – 19, 2022, 2022 National N Scale Convention. For more information visit www.nationalnscaleconvention.com. ■



BEAUTIFUL BILEVELS



CLICK HERE!

CLICKABLE ADVERTISER INDEX

[Accu-Lites](#)
[Archer Fine Transfers](#)
[Atlas Model Railroad Co.](#)
[Bachmann](#)
[Berrett Hill Trains](#)
[Black Cat Publishing](#)
[Blair Line](#)
[Canyon Creek Scenics](#)
[Coffman Graphics](#)
[Crew Call with Mike Rose](#)
[Deluxe Materials](#)
[Digitrax \(2 page spread\)](#)
[Dr.Duino](#)
[Dwarvin](#)
[East Coast Circuits](#)
[ESU LokSound](#)
[Fast Tracks](#)
[Grain Belt Models \(ISE\)](#)
[Great Decals](#)
[Humancity Junction](#)
[Inter-Action Hobbies](#)
[ITLA Scale Models](#)
[KR Models](#)
[Litchfield Station](#)
[Logic Rail Technologies](#)
[Micro-Trains Line](#)
[Miniprints.ca](#)
[Model Railroad Control Systems](#)
[Model Train Items \(2 page spread\)](#)
[Monashee Laser Engineering](#)
[Monroe Models](#)
[Mountain Subdivision Hobbies](#)
[MRH Store \(1\)](#)
[MRH Store \(2\)](#)
[MRH Store \(3\)](#)
[MRH Store \(4\)](#)
[MRH Store \(5\)](#)
[Mt. Albert Scale Lumber](#)
[NCE \(2 page spread\)](#)
[North American Railcars \(PWRS\)](#)
[Pre-Size Model Specialties](#)
[Precision Design Co.](#)
[Rails by the Bay](#)
[Rapido \(1\)](#)
[Rapido \(2\)](#)
[Ring Engineering \(1\)](#)
[Ring Engineering \(2\)](#)
[Roomettes](#)
[ScaleTrains.com](#)
[Sceniking.com](#)
[Soundtraxx](#)
[Southern Digital](#)
[Squeaky's Trains](#)
[Streamlined Backshop Services](#)
[Tam Valley Depot](#)
[The Trainmaster Inc](#)
[TrainMasters TV \(1\)](#)
[TrainMasters TV \(2\)](#)
[TrainMasters TV \(3\)](#)
[TrainMasters TV \(4\)](#)
[24 Trains.tv](#)
[Walthers](#)
[Westerfield Models](#)
[Woodland Scenics](#)

Did you see this article?



Sources of pre-wired LEDs,
any color, any size

Get the May eBook now

← click
here

In **MRH** **RUNNING**
EXTRA

Clickable "other" index

[Other – Contents](#)

[Other – Cover](#)

[Other – MRH Marketplace](#)

[Other – MRH Sponsors](#)



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)


[MRHMAG.COM](#)

[INDEX](#)


[TABLE OF CONTENTS](#)

Coming next month in MRH ...

Adding signals to Verryl Fosnight's Wyoming Division ...



The small N scale layout project takes shape (part 3) ...



Build your own train speedometer ...

Train MPH

25.99

Elapse Time

00:00:09

Start End

Start End

System

Resetting

End Start

... coming June 15th in the
June MRH

Coming next month in Running Extra ...

... all the MRH articles and ads, PLUS:

Jeff Palmer rebuilds a Roundhouse Climax (4 part series) ...



Eric Hannsman shows how to do effective pin wash weathering ...



Mike Rose models a paper mill ...

... all this and much more!

SUBSCRIBE AND SAVE UP TO 75%



REGISTER
(free)

[INDEX](#)

[TABLE OF CONTENTS](#)

[MRHMAG.COM](#)

[INDEX](#)

[TABLE OF CONTENTS](#)